

Appendix

A Graphsage (with Graph formulation)

We aim at learning universal weights, similar to GraphSAGE Hamilton *et al.* [2017], which will signify the importance of a neighbour based on some known node values and edge weights. Here we define node values as the value of the pollutant PM_{2.5} while the edges are created using latitude, longitude and datetime features. Firstly, a graph is created from the train dataset, aggregating all inputs within 500m and 30 minutes of each other into a single node. An edge is created between two nodes if they lie within 2 hours of each other. The graph then goes through two graph-based layers to learn the required weights where embeddings are learnt using the max and mean aggregation layers, followed by 3 fully connected neural network layers to predict the final pollutant value.

Let $G = (V, E, \sigma, \mathcal{A})$ be a Directed Graph with V vertices/nodes, E edges, \mathcal{A} attributes and σ as the label mapping, where

$$\sigma : V \rightarrow \mathcal{L}$$

\mathcal{L} being the set of PM_{2.5} values.

V corresponds to the spatiotemporal locations where PM_{2.5} values are known (S: Red) or desired (U: Blue), i.e. $V=S+U$. E ($e \in E$) connects the V ($v \in V$) such that

$$e_{ij} = (v_i, v_j) \mid v_i \in S \wedge v_j \in (S \vee U) \text{ and } t_{ij} \leq TimeLimit, \text{ where } t_{ij} = \text{abs}(v_i^t - v_j^t)$$

The Graph G comprises of separate connected components for different days.

$$e_{ij} = (v_i, v_j) \mid v_i \in Day_p \text{ and } v_j \in Day_q \Rightarrow p = q$$

Weight of each edge is inversely proportional to the spatial distance between the two nodes across the edge.

$$w_{ij} = \frac{1}{1+d_{ij}}, \text{ if } e_{ij} \text{ exists, where } d_{ij} = \text{haversine}(v_i, v_j)$$

Edges exist from all S nodes to each U node. No S to S edges exist.

$$e_{ij} = (v_i, v_j) \mid v_i \in S \text{ and } v_j \in U \Rightarrow |e_{ij} \forall i| = |S| \forall j$$

The graph G is of two types:

Train Graph G_{Train} : It is used for training Graphsage Neural Network.

$$v \in Day_{Train} \Rightarrow v \in S \vee U \Rightarrow |v \in S| > 0 \text{ and } |v \in U| > 0$$

The RMSE loss on the nodes $v \in U$ is used for model training.

Test Graph G_{Test} : It is used for evaluating the trained Graphsage model on unseen test day data (Day_{Test}) along with full data from known days.

$$v \in Day_{Test} \Rightarrow v \in S \vee U \Rightarrow |v \in S| > 0 \text{ and } |v \in U| > 0$$

The v is formed by taking the corresponding PM_{2.5} label L and an indicator variable I .

$$v_i = L_i | I_i$$

$$L_i \leftarrow PM_{2.5}, I_i \leftarrow 1 \forall v \in S$$

$$L_i \leftarrow 0, I_i \leftarrow 0 \forall v \in U$$

The 2 layer mean-pool and max-pool model graphsage architecture is shown in Fig. 8.

The RMSE loss of the nodes $v \in U$ (or $v \in P$ in particular) is used as the reporting metric.

For Graphsage based evaluation, out the 80% training data in 5-fold cross validation, we use 40% as *visible* set, 40% as *held-out* set, to manage edges between these two sets.




Figure 8: Graphsage model architecture.

B Complete ML Benchmarks

Table 3 shows the complete benchmark for Spatio-temporal Interpolation for different train and input configurations. An important subset of these benchmarks is presented in Fig. 5 and discussed in § 4.4 in the main paper.

Table 3: Spatiotemporal Interpolation RMSE for different configurations (* denotes partial experiments).

Algo	Config		Delhi (Day)		Canada (Day)		Canada (Year)		USA (Day)	
	Train	Input	Mean	S.D.	Mean	S.D.	Mean	S.D.	Mean	S.D.
MeanPred	-	C	65.80	2.44	3.13	1.14	5.66	1.13	13.85	3.02
IDW	ACT	ACT	39.94	2.51	2.56	0.95	4.56	1.05	10.24	2.57
	AC	AC	351.73	2.85	2.66	0.95	7.33	1.61	23.21	5.29
	C	C	25.83	2.77	2.31	0.98	4.35	0.91	10.32	2.60
RF	ACT	ACT	22.24	2.81	2.37	0.95	4.18	0.68	10.73	2.89
	AC	AC	77.30	2.67	2.69	0.98	6.05	0.93	13.93	3.20
	C	C	22.25	2.77	2.34	0.89	4.12	0.68	10.82	2.85
XGBoost	ACT	ACT	33.24	2.87	2.55	0.95	4.62	1.01	11.51	3.05
	AC	AC	65.04	2.55	2.90	0.98	6.03	0.84	14.19	3.32
	C	C	29.73	2.76	2.71	1.05	4.09	0.67	11.66	3.16
NSGP	ACT	ACT	29.11	3.84	2.57	1.09	4.41	0.89	10.39	2.69
	ACT	C	194.96	1.63	13.02	0.72	14.68	0.63	27.11	3.25
	AC	AC	69.75	3.65	2.89	0.90	5.99	0.95	13.42	3.09
	AC	C	37.46	4.63	3.17	1.12	5.25	1.22	22.14	3.46
	C	C	170.99	9.31	12.74	0.55	13.51	0.72	27.81	3.67
Graphsage	AC	C	38.63	3.89	2.96	1.25	5.37	1.13	11.66	3.29
	C	C	38.68	4.12	3.13	1.24	5.68	1.46	12.75	4.06

Table 4 shows the complete benchmark for Spatio-temporal Missing data Imputation for different train and input configurations. Missing data imputation is briefly discussed in § 4.4 in the main paper. The traditional and powerful RF (Random Forest) algorithm outperforms all other algorithms and methods.

Table 4: Missing Data Imputation RMSE for different configurations.

Algo	Config		Delhi (Day)		Canada (Day)		Canada (Year)		USA (Day)	
	Train	Input	Mean	S.D.	Mean	S.D.	Mean	S.D.	Mean	S.D.
MeanPred	-	C	65.80	2.44	3.13	1.14	5.66	1.13	13.85	3.02
IDW	ABCT	ABCT	40.06	2.51	2.56	0.95	4.56	1.05	10.19	2.57
	ABC	ABC	399.44	1.14	2.69	0.93	7.92	1.47	68.63	8.00
RF	ABCT	ABCT	22.26	2.85	2.34	0.93	4.22	0.67	9.42	2.60
	ABC	ABC	78.90	2.71	2.70	0.96	6.21	0.96	14.09	3.13
XGBoost	ABCT	ABCT	33.46	2.87	2.53	0.91	4.63	1.02	10.23	2.74
	ABC	ABC	67.66	2.55	2.94	0.96	6.19	0.87	13.84	3.12
NSGP	ABCT	ABCT	29.06	3.64	2.52	0.95	4.40	0.85	9.62	2.46
	ABC	ABC	71.27	3.16	2.81	0.91	6.09	0.88	13.38	2.97
	ABC	C	171.94	8.08	12.71	0.53	13.29	0.94	21.76	3.18
	ABCT	C	194.98	1.55	12.90	0.60	14.58	0.68	26.80	3.08
	ABT	C	195.86	3.00	13.03	0.61	14.68	0.95	27.28	2.99
	AB	C	37.63	3.87	4.15	0.92	5.43	1.09	23.19	3.10
Graphsage	ABC	C	38.53	2.94	3.15	1.30	5.46	1.11	11.78	3.56
	AB	C	38.48	2.86	3.13	1.25	5.41	1.08	11.59	3.15

Table 5 shows the complete benchmark for Spatio-temporal Forecasting for different configurations. A subset of these benchmarks is presented in Fig. 7 and discussed in § 4.4 in the main paper.

Table 5: Forecasting RMSE for different configurations.

Algo	Config	Delhi (Day)	Canada (Day)	Canada (Year)	USA (Day)
IDW	ABT	86.52	5.65	8.31	14.61
	AB	270.73	5.73	11.23	69.20
RF	ABT	110.49	5.90	8.45	14.23
	AB	89.54	6.11	10.80	14.58
XGBoost	ABT	102.68	6.69	8.23	14.25
	AB	84.15	6.51	9.84	14.52
NSGP	ABT	95.83	5.76	8.01	13.65
	AB	86.34	6.08	10.22	14.34
ARIMA	ABT	148.86	13.87	12.85	20.12
nBeats	ABT	106.41	10.88	11.84	17.05

NSGP Variance

Non-stationary GP models provides us with uncertainty (variance) values around the expected mean PM2.5 value for each expected spatio-temporal location. We find that the average variance value for Delhi dataset is huge as compared to Canada (Day) experiments. It is more challenging for a model or algorithm to correctly understand and predict the PM values for Delhi dataset. Even the USA dataset with data over a big region does not exhibit such complexity for the algorithms.

Table 6: NSGP Variance.

	Delhi (Day)	Canada (Day)	Canada (Year)	USA (Day)
Spatio-temporal Interpolation	118.73	17.29	72.94	76.34
Missing Data Imputation	142.51	20.34	113.37	72.58
Forecasting	77.38	19.96	60.89	59.76

C Anova Tests Analysis for Low Cost Sensor

In continuation to the data quality analysis presented in § 3.2, we performed Anova Tests over the data collected by DustTrak and our Low Cost Mobile sensor devices at the same location. ANOVA Navidi [2009], Analysis of Variance, is a strong statistical factorial technique which involves one dependent variable known as response variable and one or more independent variables known as factors. The factors have different levels called treatments. The ANOVA tests compare two types of variation, the variation between the sample means and the variation within the samples.

Two-way ANOVA test between DustTrak reference sensor and our low-cost mobile sensor

In relation to our low cost sensor scenario, the observed $PM_{2.5}$ values are dependent on the sensor *Type* (DustTrak vs Low Cost) and the time(*Day*) of observation. As we have two factors, we need to perform two-way ANOVA test. For the *Day* factor, we take the hourly $PM_{2.5}$ mean samples grouped over each day (24 hours) of observations.

Two-way ANOVA tests three *null* hypotheses

- (a) the means of observations grouped by factor *Type* are same
- (b) the means of observations grouped by factor *Day* are same
- (c) there is no interaction between the two factors *Type* and *Day*

Two-way ANOVA Assumptions

We make the standard assumptions of completeness, balanced design, normal distribution, similar variance, and sufficient replicates per treatment for validating ANOVA hypotheses. We take one device per sensor *Type* and same number (11) of *Day* as treatments under the two factors, with each *Type* and *Day* containing $PM_{2.5}$ samples. Fig. 9 shows the box-plot diagram with similar standard deviation for the DustTrak and our Low cost mobile sensors.




Figure 9: Mean and Standard Deviation for DustTrak and our Low Cost Mobile sensors.

Interpreting two-way ANOVA results

Table 7 shows the two-way ANOVA test results for DustTrak and our Low Cost Mobile sensor. As per Seltman [2018], the *SumSq* column represents the sum of squared deviations for each *Source* of variation. Each *Source* has a *df* (degrees of freedom) which is a measure of the number of independent pieces of information present in the deviations that are used to compute the corresponding *SumSq*. Each *MeanSq* is a variance estimate and the *SumSq* divided by the *df* for that *Source*.

Each *F*-statistic is the ratio of two *MeanSq* values. For the main effects, *Type* and *Day*, the denominators are all MSE which are pure estimates of group variance, unaffected by the validity of the null hypothesis. Each *F*-statistic is compared against its null sampling distribution to compute a *p*-value. Interpretation of each of the *p*-values depends on the corresponding null hypothesis.

Table 7: Two-way ANOVA test for DustTrak Reference Sensor vs Our Low Cost Sensor Mobile Sensor 1

Effect	Source	df	SumSq	MeanSq	F	p-value	Significance
Main	<i>Type</i>	1	197.84	197.84	2.36	0.1248	Holds hypo (a)
	<i>Day</i>	10	30204.98	3020.50	36.10	< 0.0001	Reject hypo (b)
Interaction	<i>Type*Day</i>	10	261.76	26.18	0.31	0.9778	Holds hypo (c)
Error	Residual	444	37147.11	83.66			

In the presence of an interaction (*Type*Day*), the *p-value* for the interaction is most important and the main effects *Type* and *Day* *p-values* would be ignored if the interaction is significant. This is mainly because if the interaction is significant, then some changes in both explanatory variables (*Type* and *Day*) must have an effect on the outcome $PM_{2.5}$, regardless of the main effect *p-values*. The null hypothesis for the interaction *F*-statistic supports an additive relationship between the two explanatory variables, *Type* and *Day*, in their effects on the outcome $PM_{2.5}$. If the *p-value* for the interaction is less than α (usually 0.05), then we have a statistically significant interaction.

As we have a non-significant interaction $F_{1,10} = 0.31$ with *p-value* = 0.9778 which is greater than $\alpha = 0.05$, the null hypothesis (c) holds and the *p-values* for the main effects are valid for consideration. So, we can see that the *Day* has a significant *p-value* and thus it rejects the null hypothesis (b) meaning that there is impact of different *Day*'s observation on the observed $PM_{2.5}$ sample. This outcome aligns with a common understanding regarding the varying pollution across different days.

The analysis for the main effect sensor *Type* is more encouraging. It has a non-significant *p-value* = 0.1248 which holds the null hypothesis (a) that the means of the observations of the two device *Types*, DustTrak and our Low Cost Mobile sensor, are same. Hence, our Low Cost Mobile device can be effectively used to collect $PM_{2.5}$ observations in place of the expensive DustTrak sensors.

One-way ANOVA test between DustTrak reference sensor and our low-cost mobile sensor

Though the two-way ANOVA results hold for the main effects, we still perform one-way ANOVA test for the main effect *Type* (DustTrak vs Low Cost) for the observed $PM_{2.5}$ values. We ignore the *Day* factor in this analysis, so the $PM_{2.5}$ samples are only attributed with the *Type* factor. One-way ANOVA tests for the hypothesis (a) as of two-way ANOVA and with the standard assumptions of normal distribution and similar variance.

Table 8: One-way ANOVA test for DustTrak Reference Sensor vs Our Low Cost Sensor Mobile Sensor 1

Effect	Source	df	SumSq	MeanSq	F	p-value	Significance
Main	<i>Type</i>	1	197.84	197.84	1.36	0.2445	Holds hypothesis (a)
Error	Residual	464	67613.85	145.72			

Table 8 presents the results for one-way ANOVA, which too shows *Type* factor to have a non-significant *p-value* = 0.2445 which holds the null hypothesis (a). Hence with similar means of the observations, our Low Cost Mobile device can replace the expensive DustTrak sensors.

Two-way ANOVA test for our Low Cost device replaceability

We also show that our Low Cost Mobile devices are replaceable by each other. We perform two-way ANOVA tests between our Low Cost Mobile devices and the results are presented in Table 9.

As the *p-value* for the interaction is non-significant, main effects are valid. Likewise *Day* factor rejects hypothesis (b) and importantly *Type* factor holds hypothesis (a), allowing our Low Cost devices to replace each other as applicable.

Table 9: Two-way ANOVA test for Our Low Cost Sensor Mobile Sensor 1 vs 2

Effect	Source	df	SumSq	MeanSq	F	p-value	Significance
Main	<i>Type</i>	1	145.65	145.65	1.65	0.1991	Holds hypothesis (a)
	<i>Day</i>	10	31204.66	3120.47	35.43	< 0.0001	Reject hypothesis (b)
Interaction	<i>Type*Day</i>	10	148.46	14.85	0.17	0.9982	Holds hypothesis (c)
Error	Residual	450	39632.11	88.07			

D Spatio-temporal Correlation and Covariance Analysis

To analyze the temporal correlation over the $PM_{2.5}$ values for different locations, we split the data in grids of 1km x 1km x 1hr and average the $PM_{2.5}$ values in each grid to get a representative value¹.

We observe high autocorrelation for different spatial grid locations, for 1 hour lag. In Fig. 10, we show the autocorrelation for 12 spatial grid locations, denoted as locations A-L, with the corresponding Latitude-Longitude marked alongside in the titles. The X and Y axis represent the $PM_{2.5}$ values for without lag ($y(t)$) and with 1 hour lag ($y(t+1)$) respectively.




Figure 10: autocorrelation for 12 grid locations for 1 hour lag (the titles contain the latitude-longitude of the grid locations).

The autocorrelation decreases for lags of 2 hour or more at individual grid locations.




Figure 11: autocorrelation for 12 grid locations up to 1.5 days lags.

¹This dataset version is available at [https://huggingface.co/datasets/sachin-iitd/DelhiPollDataset/tree/main/4.Grid\(PM+Met\)](https://huggingface.co/datasets/sachin-iitd/DelhiPollDataset/tree/main/4.Grid(PM+Met))

We further analyze the hourly data for 1.5 days for individual locations, and observe patterns of high and low autocorrelation. Fig. 11 shows autocorrelation for the same 12 grid locations for 36 hours. We observe a high autocorrelation at 24 hour period indicating similar pollution traits at the same time next day. We further observe that most locations (except A and B) exhibit a local high autocorrelation in the sub 12 or 8 hour periods as well, indicating repeated traffic patterns, like similar pollution characteristics around the morning and evening periods.




Figure 12: autocorrelation for A and C grid locations for up to 7 days lags. The autocorrelation decreases with increasing the lag.

The locations A and B seem to exhibit behaviour different from other locations, with low autocorrelation in the sub 12 hours period. Both these locations are adjacent to *Kushak Nalla Bus Depot* which hosts the buses for stopping between the runs and for overnight stopping while the bus services are down. Hence more data is collected here for longer periods which shows different pollution traits compared to all other grid locations. For grid locations A and C, Fig. 12 shows the autocorrelation for the two distinct behaviour for 7 days lags. The autocorrelation for 7 days for grid locations A and C is also presented as heat-map in Fig. 13.




Figure 13: autocorrelation for A and C grid locations for up to 7 days lags as heat-map. The autocorrelation decreases with increasing the lag.

We also analyze the covariance among the spatial grid locations. In Fig. 14, we observe low or different covariances for locations at same distance from the base location. Hence there are different pollution traits at different locations, which sometimes match with neighboring locations due to common local/global factors, and sometimes differ due to some local factors.




Figure 14: Interpolated empirical covariance between a base locations and other (99) grid locations in Delhi dataset. In the first plot, all the locations around the base location A has very low covariance with A. In the second plot, the locations at same distance from the base location G have different covariance w.r.t. G.

E Meteorological Factors (Temperature, Relative Humidity, Wind Speed) Analysis

A recent research Yang *et al.* [2020] focuses the effect of meteorological factors on the pollution traits in Shenyang, China to understand temporal-spatial characteristics of particles and analyze the causality factors. Similarly, we analyzed the given dataset for the impact of the collected meteorological parameters - Temperature and Relative Humidity (RH).

We also purchased Wind Speed (WS) data for the 3 months (Nov 2020 - Jan 2021) from *www.windfinder.com*, and received data with half-hourly frequency for IGI Airport. Data has wind speed in knots varying from 0 to 19, with maximum daily average being ~ 7 knots. This wind data is not very fine, it has compromised precision with integer values only with some values missing. Still we could use this to analyze the effect of wind speed on the pollution.

Table 10: Correlation of Temperature, RH and WS with PM values.

	Temperature	Relative Humidity (RH)	Wind Speed (WS)
PM ₁	-0.305	0.323	-0.508
PM _{2.5}	-0.303	0.332	-0.480
PM ₁₀	-0.317	0.335	-0.477

Table 10 shows the correlation of temperature, humidity and WS with PM values. Overall we observe a negative correlation of PM with temperature, positive correlation of PM with RH, and negative correlation of PM with WS. Other researchers, like Yang *et al.* [2020]; Liu *et al.* [2020]; Avdakovic *et al.* [2016], have also observed similar positive and negative correlations, which is intuitive as temperature expands the air reducing PM per unit volume, humidity/moisture intensifies it, and wind blows it away. However, at a given time, which meteorological factor among these three will dominate needs more complex ML modeling.




Figure 15: Meteorological factors vs $PM_{2.5}$ over the 3 months. The orange vertical lines show the relation of high or low $PM_{2.5}$ with WS, temperature and RH. The red box shows the situation of very high $PM_{2.5}$ which is explained with non-meteorological causes.

Fig.15 shows the average wind speed, temperature and humidity for the 3 months with the corresponding average $PM_{2.5}$ values. We observe high WS with low PM on Nov 16 and low WS with high PM on Nov 24 and Jan 19, which matches the intuition. But there are adverse situations of high WS with high PM on Dec 6, and low WS with low PM on Jan 21 which doesn't match the intuition.

The initial days of November show very high pollution spikes with stable winds. As per Weather [2020], there was *high moisture, calm winds and stubble burning around the beginning of November 2020*. As per HT [2020], in 2020, Delhi had six consecutive *severe* days from November 5-10, the longest *severe* spell seen in the city since 2016. A combination of multiple factors affected this, including a prolonged and intensive stubble burning season that started early on and in high incidence, the firecracker bursting festival and unfavourable meteorological conditions.

Due to such severe pollution situation in Delhi-NCR around winters, CAQM [2022] revised their action plan for (a) *Very Poor* Air Quality to avoid dust generating construction activities during months of October to January, and (b) *Severe* Air Quality to instruct individual house owners to provide electric heaters to security staff to avoid open burning.

Besides the meteorological parameters provided with the dataset, external data like below can be useful while modeling -

1. **Meteorological data from ERA5:** <https://cds.climate.copernicus.eu/cdsapp#!/dataset/reanalysis-era5-single-levels>
2. **NASA Fire count (VIIRS):** https://firms.modaps.eosdis.nasa.gov/active_fire
3. **Pollution Data from other sources:** OpenAQ: (openaq.org), CPCB: (cpcb.nic.in)
4. **Photochemical modelling:** www.camx.com
5. **Planetary boundary layer height:** www.nrsc.gov.in/readmore_atmosphere_planet
6. **Traffic Data from the dataset duration:** [delhi-trafficdensity-dataset.github.io](https://github.com/delhi-trafficdensity-dataset)
7. **ClimateLearn: state-of-the-art climate-data/ML-models framework:** Nguyen *et al.* [2023b]
8. **ClimaX: flexible and generalizable weather/climate deep learning model:** Nguyen *et al.* [2023a]

F Bus Route Analysis

We analyzed the Delhi dataset based on the different (13) bus routes available in the data. This is shown in Fig. 16 with the overall $PM_{2.5}$ colour-map.




Figure 16: $PM_{2.5}$ distribution for the bus-routes followed over 3 months.

The title of each subplot shows the last 4 characters of the bus-route number from the dataset, with Latitude on Y-axis and Longitude on the X-axis. In different routes, there are sub-routes which showed high $PM_{2.5}$ concentrations in this duration, which can be due to high traffic concentrations

and or other local factors. Such route level $PM_{2.5}$ concentrations can be used to recommend people which routes to choose for commute/travel. Such and many other pollution traits can be further analyzed by using our dataset in conjunction with other open source data.

We further checked the daily $PM_{2.5}$ concentrations across the 13 routes. Fig. 17 shows the mean $PM_{2.5}$ values per day, with $PM_{2.5}$ levels on the Y-axis and day number on the X-axis. The number on the right axis in each subplot denotes the bus-route number.




Figure 17: Daily $PM_{2.5}$ averages (denoted on left axis) for the different routes (mentioned on right axis) for the 3 months (x-axis). We observe some common low and high pollution periods, due to sharing of sub-routes by the buses.

As observed around the vertical lines in orange colour in Fig. 17, the different bus-routes seem to exhibit similar pollution traits due to the common paths tracked by them. We also observe the difference among different routes and hence a formal correlation analysis was performed to get better characteristics on the behaviour.




Figure 18: autocorrelation for the 13 bus-routes, for upto 2 days (48 hours) lags over hourly $PM_{2.5}$ averages. We observe positive autocorrelation in the bus-routes.

We performed the autocorrelation for the 13 bus-routes separately for hourly $PM_{2.5}$ averages. Similar to the combined route analysis done in Appendix D, we observe autocorrelation for separate bus-routes for 24 hour lags. As seen in Fig. 18, the level of autocorrelation is not same for all bus-routes, highlighting influence of local factors affecting pollution in their transit paths. Similar to overall correlation in Appendix D, we also find correlations at sub 12 hour lags as well for some of the bus-routes. autocorrelation for the 3 types of bus-routes, for upto 7 days lags over hourly $PM_{2.5}$ averages is shown in Fig. 19. We observe both positive and negative correlation in bus-route 3, almost no long-term correlation in bus-route 6 and varying but positive correlation in bus-route 11.

In contrast to the grid level autocorrelation analysis performed in Appendix D, we observed less negative autocorrelation for most of the bus-routes, which seems due to the same paths being traversed at same time each day by the buses.




Figure 19: autocorrelation for the 3 types of bus-routes, for upto 7 days lags over hourly $PM_{2.5}$ averages. Both positive and negative correlation in bus-route 3, almost no long-term correlation in bus-route 6, varying but positive correlation in bus-route 11.




Figure 20: Buses share sub-routes hence some level of correlation exists between different bus routes.

Encouraged with the autocorrelation among different routes, we check the covariance among them, taking hourly $PM_{2.5}$ averages similar to autocorrelation. In Fig. 20, we can observe some average covariance among the different routes, while some of them show very low covariance. As Buses transit through different areas of the city, their corresponding data may contain peculiar characteristics for the area. A thorough analysis to understand those peculiar characteristics in contrast with other areas can reveal significant spatial traits for the Delhi region.

G Anomaly Detection

This dataset has been created using a novel IoT network with low cost sensor platform, deployed in public buses in a developing country, the first of its kind. There are many points of faults — sensors can be faulty, internet connection can be shaky, buses might be down the faults can affect the quantity of data as well as quality. Detecting such anomalies for quick fixes is a necessity. We applied statistical analysis to detect anomalies, which involves many heuristics with manually tuned thresholds. Our findings can serve as anomaly ground truth for this dataset. Automating this process with ML based methods (instead of manually tuned thresholds) can open up new avenues of anomaly detection in mobile and IoT networks. ML researchers can try and automate the fault detection process using our dataset and the ground truth anomalies. They can also modify our released code, to change our empirical thresholds for more or less aggressive anomaly definition. Additionally unsupervised learning methods perhaps would change the anomalies detected manually by us. We describe next the different anomaly metrics that we compute on the dataset using statistical analysis and empirically determined thresholds.




Figure 21: (a) Sampling rate i.e. number of samples recorded per minute for 3.12.2020. This helps us in finding out if any device isn't sampling properly. (b) Illustration of a sample box plot and process of collecting median, 25th percentile and 75th percentile in metric 1 and 2.

Anomaly metric 1: Samples recorded per minute: This metric checks for faulty devices which might be sampling more or less than expected rate. Fig. 21a shows ideal samples collected per minute should be around 20. If it deviates too much, that device is anomalous. The amount of deviation allowed is calculated statistically by observing the distributions for several days. Our algorithm (detailed in the supplementary section) finds the upper bounds and lower bounds of the median ($\Theta_{50}^L, \Theta_{50}^U$), 25th percentile ($\Theta_{25}^L, \Theta_{25}^U$) and 75th percentile ($\Theta_{75}^L, \Theta_{75}^U$) of the expected distribution. Anomaly is reported if any two of the three bounds are violated.

Anomaly metric 2: Number of minutes each device is active in an hour: A device can be active for all the 60 minutes of an hour or less based on time of the day/lunch break, stoppage at bus depots etc. So again we tried plotting the box plots for the distributions across the days and devices. We observe that ideally device should be active for 60 minutes of an hour, if the bus was taking a trip in that hour. So we used the same technique used in Metric 1: find the upper bounds and lower bounds of the median ($\Theta_{50}^L, \Theta_{50}^U$), 25th percentile ($\Theta_{25}^L, \Theta_{25}^U$) and 75th percentile ($\Theta_{75}^L, \Theta_{75}^U$) of the expected distribution. Anomaly is reported if any two of the three bounds are violated.

Anomaly metric 3 : Number of active hours in a day: An active hour for a particular sensor is any hour in which the sensor sends at least a fixed number(γ) of samples. The number of active hours should ideally be greater than a threshold value(τ). But it is hard to fix one τ across all sensors, as different buses have different schedules and frequencies, which also can change over time. This is shown by the bar plots of number of active hours in Fig 22.

So, we define τ or ideal number of active hours for every sensor as the maximum of 10 active hours and 15th percentile of the sensor's previous 15 days' active hours. This ensures that τ is appropriately chosen for every sensor depending on its particular bus's recent schedule. If the number of active hours for a sensor on any day doesn't satisfy the threshold (τ), it is reported as anomalous for the day.




Figure 22: Number of active hours for different devices on two different days as shown by two different plots. We can see that the number of active hours on both days for each device are different.

Anomaly metric 4: Samples recorded per region: It is important to check whether daily around same number of data points are collected or not in an area. This metric detects situations where bus may not complete its scheduled trip due to mechanical breakdowns or high traffic resulting in less recording of data points in some areas. We divided the area covered by buses into 16 square regions. Given total number of data points collected in each region on a day, a region is reported as anomalous if its value deviates from past seven days average of that region by at least $\delta\%$. The value of δ is calculated by observing the data of several days.

Anomaly metric 5: Inter-sensor PM values variation: Ideally the PM values measured by different sensors should lie in a close range if the measurements were carried out at the same location and time. Every night from 0 AM IST to 5 AM IST all the buses remain parked at the same bus depot. We have used the PM value data from this time period to find devices whose PM 2.5 value measurements deviate from the general PM value trend of majority devices. For each hour, we have a box plot describing PM value distributions of all the devices as shown in Fig. 23a. Let Θ_{25} and Θ_{75} represents 25th and 75th percentile of distribution of PM values of a device during an hour. Interquartile range (IQR) is defined as $(\Theta_{75} - \Theta_{25})$. Given a box plot, a device is flagged for possible anomalous behaviour if it's IQR is very high (e.g. device e6811 in Fig. 23a). In order to define how much IQR should be considered high to be flagged, we define a threshold max_IQR which is set as 90 percentile of all the IQRs of all the devices in training set. Secondly, if a box (middle 50% data) of a device in the plot varies in a range different than the range of other devices then also the device is flagged (e.g. device bc0b0 in Fig 23a). To find such anomalies, we first find a range in which boxes of majority devices lie, then all those devices which are out of this range are flagged. A parameter called 'buffer' is defined statistically based on training data for finding the range. Given a PM value distribution of an hour, we iteratively calculate candidate range as $[\Theta_{25} - \text{buffer}, \Theta_{75} + \text{buffer}]$ for each device. The candidate range which contains the boxes of maximum number of devices is considered as the final range. The devices whose box does not fit completely in this range are flagged for that hour. Finally a device is reported as anomalous if its get flagged for at least three hours in a day.




Figure 23: (a) shows a box plot of PM value distributions of various devices on 2020-12-20 4:00 AM IST. Red lines indicate the majority PM range. Device bc0b0 is flagged as it is out of majority PM range while device e6811 is flagged as its IQR exceeds max_IQR . They will be declared as anomaly if they show this behaviour in at least two more hours. (b) shows PM value distributions of the device f0aa8 on 2021-01-16. The device is reported as anomaly as its PM value measurements are highly varying across several hours.

Anomaly metric 6: Intra-sensor PM values variation: Similar to the above metric, intra sensor analysis verifies that the variation in a device’s PM value recordings across consecutive hours is not very high. Given a device’s PM value recordings during 0 AM IST to 5 AM IST, it is flagged for further checks if IQR of the device during any hour is greater than max_IQR or if at least three boxes lie out of majority PM range. The majority PM range is the PM value range which contains the maximum number of boxes computed similarly as described in the above metric except that the value of buffer here is computed based on intra sensor PM value distributions. Finally a device is reported as anomalous only if its get flagged for at least three hours in a day. Figure 23b shows one such anomaly.

We detail the heuristics for computing the above six anomaly metrics, the thresholds and summary statistics of all anomalies found, in the supplementary section and the website. The anomalies found in the paper were cross-checked with the platform vendor Aerogram and the deployment partner, the public bus company DIMTS, for correctness and usefulness. All cases on inter-sensor and intra-sensor variations (metrics 5 and 6) were caused by local electrical maintenance work in a particular bus at the depot, whose sensor readings deviated from other buses in the depot. Lack of samples per minute or per hour (metrics 1 and 2) are helping to understand 4G networking issues. Finally the metrics for active hours per day and spatial coverage consistency (metrics 3 and 4) are helping to gain insights on unpredictable public bus behavior in Delhi, especially during Covid-19 induced lockdowns, where bus schedules and routes are seeing significant variations. Thus all these anomalies are highly important to gain insights about a live IoT network deployment. Defining these metrics and the multiple thresholds for them has been cumbersome, and more automated ML methods using this dataset and our findings as ground-truth, will be immensely valuable.

H Miscellaneous

We also observed the output of Spatio-temporal Interpolation using Random Forest (RF) algorithm to see the distribution of RMSE for the predictions. Fig. 24 shows some locations with large error, which needs indicates need of special handling.




Figure 24: RMSE of the Spatio-temporal Interpolation using RF. (a) bigger circle denotes bigger RMSE for the spatial location while modeling. (b) shows the RMSE distribution. Few locations are hard to model.

I Letters of Approval / Certifications from authorities

I.1 ICAT EMC certification

ICAT EMC certification of our instrument verifying that it doesn't interfere with the bus's electro-mechanical properties.



INTERNATIONAL CENTRE FOR AUTOMOTIVE TECHNOLOGY
[A Division of NATRIP Implementation Society (NATIS), Govt. of India]

Non-Transferable

TEST REPORT

ULR No. : **T C 5 3 6 0 1 9 0 5 0 0 0 0 3 9 6 F** Date: 12-09-2019

Test Report No.: **C D 0 M 0 0 4 7 4**

1.0 NAME AND ADDRESS OF THE CUSTOMER : Computer Science Department IIT Delhi
Room 514, Bharti Building IIT Delhi Hauz Khas New Delhi-110016
New Delhi INDIA
CUSTOMER REFERENCE : CCDCSDIOHEMC70648; Dated: 17-07-2019

2.0 DESCRIPTION OF TEST PROPERTY :
DUT Name : Aerogram
Model Name : Aerogram
Voltage system: 24V DC
Part No. : 01
Drawing No : EzioMotiv – V1.0

3.0 DATE OF RECEIPT OF TEST PROPERTY: 03-09-2019

4.0 CONDITION OF SAMPLE: Sample received in good condition.

5.0 TEST OBJECTIVE: To conduct tests as mentioned in Sr. No. 13 on DUT as per AIS004 - Part 3 as amended up to April 2015.

6.0 TEST METHOD: As per AIS004 - Part 3 as amended up to April 2015.

7.0 ANY DEVIATION OR EXCLUSION FROM TEST METHOD: NA

8.0 FUNCTIONAL VERIFICATION: DUT was powered on with 27 V DC (24 V DC system) for all tests as per AIS 004-3 as amended up to April 2015. Performance was observed by monitoring data strings before and after each test and during the test, and power LED of the device was monitored.

9.0 CONCLUSION: The component mentioned in Sr. No. 2 above meets the requirements as per AIS004 - Part 3 as amended up to April 2015.

10.0 TEST DESCRIPTION: EMC/EMI testing as per AIS004 - Part 3 as amended up to April 2015 on the DUT.

11.0 DATE OF PERFORMANCE OF TEST: 09-09-2019 ; 10-09-2019


12.0 LOCATION OF TEST: ICAT EMC LAB, Manesar

13.0 TEST RESULTS:

Sr. No.	TEST TITLE	SAMPLE ID	REF. STD.	OBSERVATIONS/RESULTS
1	Radiated Emission	ICAT/EMC/70648/01	AIS004- Part 3: 2009 as amended up to April 2015	Refer Annexure-I
2	Radiated Immunity			Refer Annexure-II
3	Conducted Transient Emission			Refer Annexure-III
4	Conducted Transient Immunity			Refer Annexure-IV

Refer Annexure-V for test setup photographs.

Disclaimer:
This test report pertains only to the test samples / components / parts of assembled product submitted to ICAT in the present condition based on the documents / information provided / submitted by the customer. The issuance of this test report does not include any measure of approval, certification, supervision, ODR, control of quality surveillance by ICAT of the test samples / parts of components. No extent, obligation or attribution from this test report may be published or used to advertise the product without the written consent of the Director, ICAT, who reserves the absolute right to require a report of any of the details of engineering drawings for the test components may be sought. ICAT is not responsible for any change or error of any design or specification or any other information, which may be based on other sources, will be sole responsibility of the customer. ICAT shall not be held liable for any claims or damages made by the customer, whatsoever. The customer shall alone be liable for the same and undertake to indemnify ICAT in this regard. Further, ICAT has the right to initiate cancellation / withdrawal of the certificate / report issued, in case of any fraud, misrepresentation, when it comes to the knowledge of ICAT. The acceptance of test samples / components shall be the responsibility of the customer, reference is made to the terms and conditions of the contract.

Prepared By	Checked By	Approved By
 JEEVAN PAL Deputy Manager	 NIKHIL GROVER Manager	 S. K. KALIA CBO-ICAT Centre-II



Page 1 of 6
+
Dwg-01
[70648]

Office Address : Centre-I : Plot No.-26, Sector-3, HSIIDC, IMT-Manesar, Gurugram-122050. Haryana (India)
Centre-II : Plot No.-01, Sector-M-11, HSIIDC, IMT-Manesar, Gurugram-122050. Haryana (India)
Phone : 0124-4586111, Fax : +91-124-2290005. E-mail: team@icat.in, Website : www.icat.in
(An ISO 9001, ISO 14001 and ISO 45001 certified, scope wise NABL accredited and BIS recognised Test House)

Innovation • Service • Excellence

T C 5 3 6 0 1 9 0 5 0 0 0 0 3 9 6 F Date: 12-09-2019

C D 0 M O 0 4 7 4



14.0 CLASSIFICATION OF FUNCTIONAL STATUS:

CLASSIFICATION OF FUNCTIONAL STATUS AS PER (A.4) ANNEX-A, ISO 7637-2:2004:	
CLASSES	DESCRIPTION
<u>CLASS A</u>	All functions of the device/system perform as designed during and after the test.
<u>CLASS B</u>	All functions of the device/system perform as designed during the test. However, one or more may go beyond the specified tolerance. All functions return automatically to within normal limits after the exposure is removed.
<u>CLASS C</u>	One or more functions of a device/system do not perform as designed during the test but return automatically to normal operation after the exposure is removed.
<u>CLASS D</u>	One or more functions of a device/system do not perform as designed during the exposure and do not return to normal operation until exposure is removed and the device/system is reset by simple 'operator/use' action.
<u>CLASS E</u>	One or more functions of a device/system do not perform as designed during and after exposure and cannot be returned to proper operation without repairing or replacing the device/system.

15.0 LIST OF EQUIPMENTS USED IN THE TEST AND CALIBRATION DETAILS:

Lab ID	Name of Instruments	Manufacturer	Model (S. No.)	Calib. due date
Radiated Emission				
ICAT/EMC/TR - 01	EMI Test Receiver	Rohde and Schwarz	ESU-8 (100290)	03/05/2020
ICAT/EMC/EPA-01	External Preamplifiers	TDK RF Solutions	PA-02-001-100 (121054)	03/05/2022
ICAT/EMC/OFBA-04	Biconical Antenna with polarization adaptor	TDK RF Solutions	PBA2030 (130818)	09/05/2021
ICAT/EMC/OFBA-05	Broadband Log periodic Antenna	TDK RF Solutions	PLP 3003 (130830)	09/05/2021
ICAT/EMC/AN-01	LISN	Schwarzbeck	NNBM8124 (8124-649)	03/05/2022
ICAT/EMC/AN-02		Schwarzbeck	NNBM8124 (8124-650)	03/05/2022
Radiated Immunity				
ICAT/EMC/SG-01	Signal Generator	Agilent Technologies	N5183A-520 (50140523)	29/04/2022
ICAT/EMC/SG-03		Agilent Technologies	SMB100A (103955)	30/04/2022
ICAT/EMC/AN-01	LISN	Schwarzbeck	NNBM8124 (8124-649)	03/05/2022
ICAT/EMC/AN-02		Schwarzbeck	NNBM8124 (8124-650)	03/05/2022
ICAT/EMC/CIP-02	Current injection probe	FCC	F-140 (130055)	-
ICAT/EMC/OFBA-07	V Log Array Antenna	TDK RF Solutions	VLA-8001 (130835)	-
ICAT/EMC/OFBA-10	Horn Antenna	TDK RF Solutions	ATH800M5GA (0337348)	-
ICAT/EMC/PM-01	RF Power Meter	Agilent Technologies	N1914A (MY50000499)	30/04/2022
ICAT/EMC/PM-03		Agilent Technologies	N1912A (MY54010017)	30/04/2022
ICAT/EMC/AMP-01	Amplifier	AR	500W1000A (0335094)	-
ICAT/EMC/AMP-02		AR	2500A225, Sr. No. 338773	-
ICAT/EMC/AMP-03		AR	500T1G2 (0336388)	-
ICAT/EMC/APS-01	Average Power sensor (9kHz-6GHz)	Agilent Technologies	E9304 (S.No. MY51020021)	30/04/2020
ICAT/EMC/APS-02		Agilent Technologies	E9304 (S.No. MY51030004)	30/04/2020
ICAT/EMC/PS-01	Power Sensor (50MHz-18GHz)	Agilent Technologies	N1921A (MY53380017)	30/04/2020
ICAT/EMC/PS-02		Agilent Technologies	N1921A (MY53380020)	30/04/2020
ICAT/EMC/FP-06	Field Probe	AR	FL7018 (0334718)	30/09/2020
Conducted Transient Emission				
ICAT/EMC/PG/05	Voltage drop simulator	EM test	VDS 200N100	21/01/2020
ICAT/EMC/DSO/01	Digital Storage Oscilloscope	EM test	DSO9254A	21/01/2020
ICAT/EMC/AN/01	Single line artificial network	EM test	AN 200N100	21/01/2020
ICAT/EMC/SW/01	Electronic switch	EM test	BS 200N100	21/01/2020
ICAT/EMC/MR/01	Matching resistor for transient generators	EM test	CAISO	21/01/2020
Conducted Transient Immunity				
ICAT/EMC/PG/02	Ultra-Compact Simulator	EM test	UCS 200N100	21/01/2020
ICAT/EMC/PG/05	Voltage drop simulator	EM test	VDS 200N100	21/01/2020
ICAT/EMC/PG/05	Load dump simulator	EM test	LD200N	21/01/2020

Innovation • Service • Excellence

Prepared By	Checked By
 JEEVAN PAL Deputy Manager	 NIKHIL GROVER Manager



T	C	5	3	6	0	1	9	0	5	0	0	0	0	3	9	6	F
Date: 12-09-2019																	
C	D	0	M	0	0	4	7	4									



Annexure – I

1.0 Measurement of Radiated Emissions:


1.1 Test Condition:

Operating Condition	Powered ON
---------------------	------------

1.2 Test Specifications:

Frequency Range	30MHz - 1000MHz
Step Size	50kHz
Bandwidth	120kHz
Measurement time	5ms
Antenna	30MHz - 300MHz: Bi-conical antenna, 300MHz - 1000MHz: Log-Periodic antenna
Antenna Polarization	Horizontal and Vertical
Antenna Location	In front of centre of harness
Antenna Distance	1 meter
Detector	Peak and Average
Harness length	1700mm

1.3 Test Graphs:



1.4 Test Requirements:

Radiated Emissions measured should be within limits defined in AIS004- Part 3: 2009 as amended up to April 2015.

1.5 Test Observations /Results:

Radiated Emissions measured are within limits.

<p style="text-align: center;">Prepared By</p> <div style="text-align: center; font-size: 2em; color: blue;">Jeevan</div> <p style="text-align: center;">JEEVAN PAL Deputy Manager</p>		<p style="text-align: center;">Checked By</p> <div style="text-align: center; font-size: 2em; color: blue;">Nikhil</div> <p style="text-align: center;">NIKHIL GROVER Manager</p>
		<p>Page 3 of 6 + Dwg.-01 [70648]</p>

Innovation • Service • Excellence

Annexure – II

2.0 Radiated Immunity Test:

2.1 Bulk Current Injection (BCI):

2.1.1 Test Condition:

Operating Mode	Powered ON
----------------	------------

2.1.2 Test Specifications:

Frequency Range	20MHz – 80MHz
Step Size	5%
Current Severity Level	60mA
Dwell Time	2s
Harness length	1700mm
Current probe position	150mm from DUT
Test Method	Substitution (open loop)
Modulation	Amplitude modulation with 1 kHz modulating frequency and 80 % modulation depth.

2.1.3 Test Observations /Results:

S. No.	Frequency Range	Modulation	Acceptance Criteria	Observation/Result
1.	20MHz to 80MHz	Amplitude Modulation (AM)	No deviation in performance of DUT should be observed during test	No deviation observed

2.2 Absorber Lined Shielded Enclosure (ALSE) method:

2.2.1 Test Condition:

Operating Mode	Powered ON
----------------	------------

2.2.2 Test Specifications:

Frequency Range	80MHz – 2000MHz
Step Size	80-400MHz: 5%, 400-2000MHz: 2%
Field Severity Level	30V/m
Dwell Time	2s
Harness length	1700mm
Antenna	80MHz – 1000MHz: V log array antenna, 1000MHz – 2000MHz: Horn antenna
Antenna Polarization	Vertical
Antenna Location	80MHz – 1000MHz: in front of centre of harness, 1000MHz – 2000MHz: in front of DUT
Antenna Distance	1 meter
Test Method	Substitution
Modulation	80MHz – 800MHz: Amplitude modulation with 1 kHz modulating frequency and 80 % modulation depth 800MHz – 2000MHz: Pulse modulation: Ton: 577µs, period: 4600µs

2.2.3 Test Observations /Results:

Sr. No.	Frequency Range	Modulation	Antenna Polarization	Acceptance Criteria	Observation/Result
1.	80MHz to 800MHz	Amplitude Modulation	Vertical	No deviation in performance of DUT should be observed	No deviation observed
2.	800MHz to 1000MHz	Pulse Modulation			
3.	1000MHz to 2000MHz	Pulse Modulation			

<p style="text-align: center;">Prepared By</p> <div style="text-align: center;">  JEEVAN PAL Deputy Manager </div>		<p style="text-align: center;">Checked By</p> <div style="text-align: center;">  NIKHIL GROVER Manager </div>	Page 4 of 6 + Dwg.-01 [70648]
--	---	---	---

T	C	5	3	6	0	1	9	0	5	0	0	0	0	3	9	6	F
Date: 12-09-2019																	
C	D	0	M	0	0	4	7	4									



Innovation • Service • Excellence

Annexure – III

3.0 Measurement of Conducted Transient Emissions:

3.1 Test Condition:

Operating Condition	Powered ON
---------------------	------------

3.2 Test Observations/Results:

24V System

Sr. No.	Supply Polarity	Limits as per AIS 004:Part 3	Observation	Results
Fast transient				
1.	DUT ON to OFF	Positive: +150V Negative: -400V	Positive Transient: No Significant Transient Negative Transient: No Significant Transient	Within Limits
2.	DUT OFF to ON		Positive Transient: 42.0 V Negative Transient: No Significant Transient	Within Limits
Slow transient				
3.	DUT ON to OFF	Positive: +150V Negative: -400V	Positive Transient: No Significant Transient Negative Transient: No Significant Transient	Within Limits
4.	DUT OFF to ON		Positive Transient: 43.32V Negative Transient: No Significant Transient	Within Limits

Annexure – IV

4.0 Immunity to Transient Disturbances Conducted along Supply Lines as per AIS 004-3 as amended up to April 2015 following ISO 7637-2:2004:


4.1 DUT Condition:

Operating Condition	Powered ON
---------------------	------------

4.2 Test Requirements and Observations/Results:

24V System:

Test Pulse	Severity Level	Acceptance Criteria	Achieved Class	Observations	Results
Pulse 1	III	Class C	Class C	Reset Observed during pulse injection	Satisfactory
Pulse 2a		Class B	Class A	No deviation in performance observed	Satisfactory
Pulse 2b		Class C	Class C	Reset Observed during pulse injection	Satisfactory
Pulse 3a		Class A	Class A	No deviation in performance observed	Satisfactory
Pulse 3b		Class A	Class A	No deviation in performance observed	Satisfactory
Pulse 4		Class C	Class C	Reset Observed during pulse injection	Satisfactory

<p>Prepared By</p>  <p>JEEVAN PAL Deputy Manager</p>		<p>Checked By</p>  <p>NIKHIL GROVER Manager</p>	<p>Page 5 of 6 + Dwg.-01 [70648]</p>
---	---	--	--

T	C	5	3	6	0	1	9	0	5	0	0	0	0	3	9	6	F	Date: 12-09-2019
C	D	0	M	0	0	4	7	4										



Annexure – V

5.0 Test Setup and Test Circuitry:







Radiated Emission	
Radiated Immunity	
Bulk Current Injection	Conducted Immunity
Conducted Transient Emission	
Setup for Fast Transient	Setup for Slow Transient

----- END OF REPORT -----

Prepared By		Checked By	
JEEVAN PAL Deputy Manager		NIKHIL GROVER Manager	Page 6 of 6 + Dwg.-01 [70648]

Innovation • Service • Excellence

Parts List				
Item	Qty	Part Number	Description	Material
1	1	PI_case		Steel
2	1	PI_plate_sm		Acrylic
3	1	PI_usb_plate		Acrylic
4	1	Stm32_case		Steel
5	1	Pms7003_plate		Acrylic



Signature



Technical reference	Created by	Approved by
CSE, IIT-Delhi / AG1337	Manoj Sahukar 24-08-2019	Dr. Rijurekha Sen
Dept.	Document type	Document status
	CAD Model	In Production
	Title	DWG No.
	Aerogram	EzioMotiv V1.0
		Rev.
		12
		Date of issue
		26-8-2019
		Sheet
		1/1

I.2 Delhi Integrated Multi-Modal Transit System (DIMTS) letter of support



Ref: DIMTS/TP/2018/2756

Dated: June 21, 2018

To,
Department of Science & Technology
Delhi -

Subject : Letter of Support for the Proposed Research study.

On behalf of DIMTS, we will extend our support to Profs Pravesh Biyani and Rijurekha Sen for their research proposal related to "Vehicle mounted Particulate Matter (PM) sensing in Delhi-NCR".

DIMTS runs more than 1600 non air-conditioned cluster buses on various routes in the Delhi region. We will facilitate the use of some of the vehicle fleet as needed by the researchers for pilot studies as they build and test their vehicle mounted sensing system.

Pollution being a pressing problem in Delhi-NCR, partnering with this research effort in a meaningful way will be very exciting for DIMTS.

Thanking you.

Yours faithfully,

Samir Sharma
Vice President - Transport Planning

DELHI INTEGRATED MULTI-MODAL TRANSIT SYSTEM LTD.

(A joint venture of the Govt. of NCT of Delhi and IDFC Foundation)

An ISO 9001:2015, ISO 14001:2015, OHSAS 18001:2007 & ISO 27001 certified and CMMI appraised company
CIN No. U60232DL2006PLC148406

REGD. OFF.: 1ST FLOOR, MAHARANA PRATAP ISBT BUILDING, KASHMERE GATE, DELHI 110 006 (INDIA)
Tel: +91 11 43090100 • Fax: +91 11 23860966 • Email : info@dimts.in • Web: www.dimts.in

I.3 Delhi Pollution Control Committee (DPCC) letter of Support



F. No. DPCC | (12) (1) (260) Lab (A) 2020 | 2203

Date: 27/1/2020

To,

Dr. Rjurekha Sen
Department of Computer Science,
IIT Delhi, Hauz Khaz,
New Delhi-110016

Subject- Support Letter for Vehicle Mounted Low Cost PM Monitoring in
Delhi

Madam,

With reference to your E-mail and telephonic discussion this organization is interested to know feasibility of Vehicle Mounted Low Cost PM Monitoring in Delhi and willing to share data generated by DPCC Ambient Air Quality Network to assess error percentage of Low Cost System.



(Dr. M. P. George)

Scientist
Dr. M. P. GEORGE
Scientist

I.4 Delhi Ministry of Transport (MOT) Permission

GOVERNMENT OF NCT OF DELHI
TRANSPORT DEPARTMENT
(CLUSTER & DTC SECRETARIAT)
5/9, UNDER HILL ROAD, DELHI – 110 054

No. F.10/STA/Policy /Tpt./ 2011/333/40631

Date: 17/08/2020

To

The CEO,
Delhi Integrated Multi Modal Transit System Ltd.,
8th Floor, Block-1, Delhi Technology Park,
Shastri Park, Delhi-110053.


Subject: Request for permission to install pollution sensing units in Cluster buses as a part of R&D Project by IIT, Delhi.

Sir,

Kindly refer to your letter no. DIMTS/Road Transport/2019/4398, dated 05.11.2019, on the abovementioned subject. DIMTS had requested for a formal approval to install pollution sensing units in 10 Cluster buses by CSE IIT, Delhi.

In this context, I am directed to convey the approval of Hon'ble Minister (Transport) for installing of pollution sensing units in 10 Cluster buses of the Kushak Nalah Depot by CSE, IIT Delhi.

Yours faithfully,


(Subodh Kumar)
Deputy Commissioner
(Cluster & DTC Sectt.)

Copy to:

1. Dy. Commissioner (PCD) with reference to U.O. NO. 23(1471)/CAP/TPT/PCD/ 2018/ 1595/87542 dated 26.11.2019.
2. Ms. Rijurekha Sen, Assistant Professor, CSE, IIT, Delhi.
3. M/s. Indraprastha Logistics Pvt. Ltd, 80/2, Ground Floor Govindpuri Kalkaji New Delhi-110019

I.5 Letter of funding: SCIENCE & ENGINEERING RESEARCH BOARD (SERB), INDIA

FILE NO. IMP/2018/001481
SCIENCE & ENGINEERING RESEARCH BOARD (SERB)
 (A statutory body of the Department of Science & Technology, Government of India)
 5 & 5A, Lower Ground Floor
 Vasant Square Mall
 Plot No. A, Community Centre
 Sector-B, Pocket-5, Vasant Kunj
 New Delhi-110070

Dated: 29-Mar-2019

ORDER

Domain: Information & Comm. Technology
 Subject: Financial Sanction of the research project titled "Scalable Spatio-Temporal Measurement and Analysis of Air Pollution Data for Delhi-NCR using Vehicle-Mounted Sensors" under the guidance of Dr. Rijurekha Sen, Department of Computer Science, Indian Institute of Technology Delhi, Hauz Khas, New Delhi, DELHI-110016 and by Dr. Pravesh Biyani, Assistant Professor, Ece Dept, Indraprastha Institute Of Information Technology and by Dr. Arnab Bhattacharya, Associate Professor, Department Of Computer Science And Engineering, Indian Institute Of Technology Kanpur and by Dr. Sayan Ranu, Assistant Professor, Computer Science And Engineering, Indian Institute Of Technology Delhi - Release of 1st grant.

Sanction of Science and Engineering Research Board (SERB) is hereby accorded to the above mentioned project at a total cost of Rs. 12746800/- (Rs. One Crore Twenty Seven Lakh Forty Six Thousand Eight Hundred Only) with break-up of Rs. 5500000/- under Capital (Non-recurring) head and Rs. 7246800/- under General (Recurring) head for a duration of 36 months. The items of expenditure for which the total allocation of Rs. 12746800/- has been approved are given below:

S. No	Head	Total (in Rs.)
A	Non-recurring	
1	Equipment -> Laptop -> Server -> Sensors	5500000
A'	Total (Non-Recurring)	5500000
B	Recurring Items	
1	Recurring - I : (Manpower) Recurring - II : (Consumables, Travel, Contingencies) Recurring - III : Scientific Social Responsibility	3888000 2200000 0
2	Recurring - IV : (Overhead Charges)	1158800
B'	Total (Recurring)	7246800
C	Total cost of the project (A' + B')	12746800

2. Sanction of the SERB is also accorded to the payment of Rs. 5500000/- (Rupees Fifty Five Lakh only) under 'Grants for creation of capital assets' and Rs. 2415000/- (Rupees Twenty Four Lakh Fifteen Thousand only) under 'Grants-in-aid General' to IRD, Indian Institute Of Technology Delhi, Hauz Khas, New Delhi being the first installment of the grant for the year 2018-2019 for implementation of the said research project.

3. The expenditure involved is debit to Fund for Science & Engineering Research (FSER)
This release is being made under Impacting Research Innovation and Technology (IMPRINT-2). (PAC Information & Communication Technology)

4. The Sanction has been issued to Indian Institute Of Technology Delhi, Hauz Khas, New Delhi with the approval of the competent authority under delegated powers on 28 March, 2019 and vide Diary No. SERB/F/13078/2018-2019 dated 28 March, 2019

5. Sanction of the grant is subject to the conditions as detailed in Terms & Conditions available at website (www.serb.gov.in).

6. Overhead expenses are meant for the host Institute towards the cost for providing infrastructural facilities and general administrative support etc. including benefits to the staff employed in the project.

7. While providing operational flexibility among various subheads under head Recurring-II, it should be ensured that not more than Rs. 450000 under Travel and Rs. 450000 under Contingency should be spent.

8. As per rule 211 of GFR, the accounts of project shall be open to inspection by sanctioning authority/audit whenever the institute is called upon to do so.

9. The sanctioned equipment would be procured as per GFR and its disposal of the same would be done with prior approval of SERB.

10. The release amount of Rs. 7915000/- (Rupees Seventy Nine Lakh Fifteen Thousand only) will be drawn by the Under Secretary of the SERB and will be disbursed by means of RTGS transaction as per their Bank details given below:

Account Name	IRD ACCOUNTS IITD
Account Number	10773572600
Bank Name & Branch	STATE BANK OF INDIA IIT BRANCH, IIT HAUZ KHAS, NEW DELHI - 110016
IFSC/RTGS Code	SBIN0001077
Email id of A/C Holder	arird@admin.iitd.ac.in
Email id of PI	riju@cse.iitd.ac.in

11. The institute will furnish to the SERB separate Utilization certificate (UCs) financial year wise to the SERB for Recurring (Grants-in-aid General) & Non-Recurring (Grants for creation of capital assets) and an audited statement of

accounts pertaining to the grant immediately after the end of each financial year.

12. The institute will maintain separate audited accounts for the project. A part or whole of the grant must be kept in an interest earning bank account which is to be reported to SERB. The interest thus earned will be treated as credit to the institute to be adjusted towards further installment of the grant.

13. The project File no. IMP/2018/001481 should be mentioned in all research communications arising from the above project with due acknowledgement of SERB.

14. The manpower sanctioned in the project, if any is co-terminus with the duration of the project and SERB will have no liability to meet the fellowship and salary of supporting staff if any, beyond the duration of the project

15. As this is the first grant being released for the project, no previous U/C is required.

16. The institute may refund any unspent balance to SERB by means of a Demand Draft favoring "FUND FOR SCIENCE AND ENGINEERING RESEARCH" payable at New Delhi.

17. The organization/institute/university should ensure that the technical support/financial assistance provided to them by the Science & Engineering Research Board should invariably be highlighted/ acknowledged in their media releases as well as in bold letters in the opening paragraphs of their Annual Report.

18. In addition, the investigator/host institute must also acknowledge the support provided to them in all publications, patents and any other output emanating out of the project/program funded by the Science & Engineering Research Board.

Monika Agarwal
(Dr. Monika Agarwal)
Scientist E
ms.imprint@gmail.com

To,
Under Secretary
SERB, New Delhi

Copy forwarded for information and necessary action to: -

1.	The Principal Director of Audit, A.G.C.R. Building, IInd Floor I.P. Estate, Delhi-110002
2.	Sanction Folder, SERB, New Delhi.
3.	File Copy
4.	<p>Dr. Rijurekha Sen Department of Computer Science Indian Institute of Technology Delhi, Hauz Khas, New Delhi, DELHI-110016 Email: riju@cse.iitd.ac.in Mobile: 919810591052</p> <p>Dr. Pravesh Biyani ECE Dept Indraprastha Institute Of Information Technology</p> <p>Dr. Arnab Bhattacharya Department Of Computer Science And Engineering Indian Institute Of Technology Kanpur</p> <p>Dr. Sayan Ranu Computer Science And Engineering Indian Institute Of Technology Delhi (Start date of the project may be intimated by name to the undersigned. For guidance, terms & Conditions etc. Please visit www.serb.gov.in.)</p>
5.	IRD, Indian Institute Of Technology Delhi, Hauz Khas, New Delhi (Receipt of Grant may be intimated by name to the undersigned)
6.	Secretary, Department of Science & Technology Ministry of Science and Technology Technology Bhavan, New Mehrauli Road, New Delhi-110016 Email: dstsec@nic.in
7.	Secretary (Higher Education) Ministry of Human Resource Development Shastri Bhavan, New Delhi- 110 001 Email: secy.dhe@nic.in

Monika Agarwal
(Dr. Monika Agarwal)
Scientist E
ms.imprint@gmail.com