LEARNING TO INFER GRAPHICS PROGRAMS FROM HAND-DRAWN IMAGES

Anonymous authors
Paper under double-blind review

ABSTRACT

We introduce a model that learns to convert simple hand drawings into graphics programs written in a subset of LaTeX. The model combines techniques from deep learning and program synthesis. We learn a convolutional neural network that proposes plausible drawing primitives that explain an image. These drawing primitives are like a trace of the set of primitive commands issued by a graphics program. We learn a model that uses program synthesis techniques to recover a graphics program from that trace. These programs have constructs like variable bindings, iterative loops, or simple kinds of conditionals. With a graphics program in hand, we can correct errors made by the deep network, measure similarity between drawings by use of similar high-level geometric structures, and extrapolate drawings. Taken together these results are a step towards agents that induce useful, human-readable programs from perceptual input.

1 INTRODUCTION

How can an agent convert noisy, high-dimensional perceptual input to a symbolic, abstract object, such as a computer program? Here we consider this problem within a graphics program synthesis domain. We develop an approach for converting hand drawings into executable source code for drawing the original image. The graphics programs in our domain draw simple figures like those found in machine learning papers (see Fig. 1a).



Figure 1: (a): Model learns to convert hand drawings (top) into LaTeX (rendered below). (b) Synthesizes high-level *graphics program* from hand drawing.

The key observation behind our work is that generating a programmatic representation from an image of a diagram actually involves two distinct steps that require different technical approaches. The first step involves identifying the components such as rectangles, lines and arrows that make up the image. The second step involves identifying the high-level structure in how the components were drawn. In Fig. 1(b), it means identifying a pattern in how the circles and rectangles are being drawn that is best described with two nested loops, and which can easily be extrapolated to a bigger diagram.

We present a hybrid architecture for inferring graphics programs that is structured around these two steps. For the first step, our approach uses a deep network to infer a set of primitive shape-drawing

commands. We refer to this set as a *trace set* since it corresponds to the set of commands in a program's execution trace but lacks the high-level structure that determines how the program decided to issue them. The second step involves synthesizing a high-level program capable of producing the trace set identified by the first phase. We achieve this by *constraint-based program synthesis* (Solar Lezama, 2008). The program synthesizer searches the space of possible programs for one capable of producing the desired trace – inducing structures like symmetries, loops, or conditional branches. Although these program synthesizers do not need any training data, we show how to learn a *search policy* in order to synthesize programs an order of magnitude faster than constraint-based synthesis techniques alone.

Images are high-dimensional and unstructured while programs are high-level and symbolic. We resolve this mismatch by advancing a new model of collaboration between these two representations, which we call The Trace Hypothesis:

The Trace Hypothesis. The set of commands issued by a program, which we call a *trace set*, is the correct liaison between high-dimensional unstructured perceptual input and high-level structured symbolic representations.

The roadmap of our paper is structured around the trace hypothesis, as outlined in Fig. 2.



Figure 2: Both the paper and the system pipeline are structured around the *trace hypothesis*

The new contributions of this work are: (1) A model that converts sketches to high-level programs: in contrast to converting images to vectors or low-level parses (Huang et al., 2017; Nishida et al., 2016; Wu et al., 2017; Beltramelli, 2017; Deng et al., 2017). (2) An algorithm for learning a policy for efficiently searching for programs, building on Levin search (Levin, 1973) and generalizing recent work like DeepCoder (Balog et al., 2016). (3) The trace hypothesis: a framework for going from perception to programs, which connects this work to other models of program induction that use traces, like the Neural Program Interpreter (Reed & de Freitas, 2015).

2 NEURAL ARCHITECTURE FOR INFERRING TRACE SETS

We developed a deep network architecture for efficiently inferring a trace set, T, from an image, I. Our model is a combination of ideas from Neurally-Guided Procedural Models (Ritchie et al., 2016) and Attend-Infer-Repeat (Eslami et al., 2016). Our model constructs the trace one drawing command at a time. When predicting the next drawing command, the network takes as input the target image I as well as the rendered output of previous drawing commands. Intuitively, the network looks at the image it wants to explain, as well as what it has already drawn. It then decides either to stop drawing or proposes another drawing command to add to the trace; if it decides to continue drawing, the predicted primitive is rendered to its "canvas" and the process repeats.

Fig. 3 illustrates this architecture. We first pass a 256×256 target image and a rendering of the trace so far (encoded as a two-channel image) to a convolutional network. Given the features extracted by the convnet, a multilayer perceptron then predicts a distribution over the next drawing command to add to the trace; see Tbl. 1 for the drawing commands we currently model. We predict the drawing command token-by-token,[1] conditioning each token both on the image features and on the

[1]Tokens are atomic symbols in the programming language – so the model is *not* predicting lines of code character-by-character, but instead the model knows about the syntactic structure of primitive drawing commands



Figure 3: Our neural architecture for inferring the trace set of a graphics program from its output. Blue: network inputs. Black: network operations. Red: samples from a multinomial. `Typewriter font`: network outputs. Renders snapped to a 16×16 grid, illustrated in gray. STN (spatial transformer network) is a differentiable attention mechanism (Jaderberg et al., 2015).

Table 1: Primitive drawing commands currently supported by our model.

`circle`(x, y)	Circle at (x, y)
`rectangle`(x_1, y_1, x_2, y_2)	Rectangle with corners at (x_1, y_1) & (x_2, y_2)
`line`$(x_1, y_1, x_2, y_2,$ arrow $\in \{0, 1\}$, dashed $\in \{0, 1\})$	Line from (x_1, y_1) to (x_2, y_2), optionally with an arrow and/or dashed
`STOP`	Finishes drawing command inference

previously generated tokens. We also use a differentiable attention mechanism (Spatial Transformer Networks: Jaderberg et al. (2015)) to let the model attend to different regions of the image while predicting each token. In Fig. 3 the network first decided to emit the `circle` token conditioned on the image features, then it emitted the x coordinate of the circle conditioned on the image features and the `circle` token, and finally it predicted the y coordinate of the circle conditioned on the image features, the `circle` token, and the x coordinate. We currently constrain coordinates to lie on a discrete 16×16 grid, but the grid could be made arbitrarily fine. See supplement for the full details of the architecture, which we implemented in Tensorflow (Abadi et al., 2015).

We train the network by sampling trace sets T and target images I for randomly generated scenes and maximizing the likelihood of T given I with respect to the model parameters, θ, by gradient ascent. We trained the network on 10^5 scenes, which takes a little less than a day on an Nvidia TitanX GPU.

Training does not require backpropagation across the sequence of drawing commands: drawing to the canvas 'blocks' the gradients, effectively offloading memory to an external visual store. This approach is like an autoregressive version of Attend-Infer-Repeat (Eslami et al., 2016), but critically, without a learned recurrent memory state, e.g. an RNN. We can do without an RNN because we learn from ground truth (image, trace) pairs. This allows us to handle scenes with many objects without worrying about the conditioning of gradients as they propagate over long sequences, and makes training more straightforward: it is just maximum likelihood estimation of the model parameters.

Our network can "derender" random synthetic images by doing a beam search decoding to recover trace sets maximizing $\mathbb{P}_\theta[T|I]$. But, if the network makes a mistake (predicts an incorrect drawing command), it has no way of recovering from the error. To derender an image with n objects, it must correctly predict n commands – so its probability of success will decrease exponentially in n, assuming it has a nonzero chance of making a mistake. For added robustness as n becomes large, we treat the neural network outputs as proposals for a Sequential Monte Carlo (SMC) sampling scheme (Doucet et al., 2001). For the SMC sampler, we use pixel-wise distance as a surrogate

for a likelihood function. The SMC sampler is designed to produce samples from the distribution $\propto L(I|\text{render}(T))\mathbb{P}_\theta[T|I]$, where $L(\cdot|\cdot)$: image$^2 \to \mathbb{R}$ uses the distance between two images as a proxy for a likelihood. Unconventionally, the target distribution of the SMC sampler includes the likelihood under the proposal distribution. Intuitively, both the proposal distribution and the distance function offer complementary signals for whether a drawing command is correct.



Figure 4: Parsing LaTeX output after training on diagrams with $\leq$ 12 objects. It generalizes to scenes with many more objects. Neither the stochastic search nor the neural network are sufficient on their own. # particles varies by model: we compare the models *with equal runtime* ($\approx$ 1 sec/object)

Fig. 4 compares the neural network with SMC against the neural network by itself or SMC by itself. Only the combination of the two passes a critical test of generalization: when trained on images with ≤ 12 objects, it successfully parses scenes with many more objects than the training data. We compare with a baseline that models the problem as image captioning (LSTM in Fig. 4). Given the target image, this baseline produces the trace in one shot by using a CNN to extract features of the input which are passed to an LSTM which finally predicts the trace token-by-token. This architecture is used in several successful neural models of image captioning (e.g., Vinyals et al. (2015)), but, for this domain, does not suffice to parse cluttered scenes with many objects.

2.1 Generalizing to hand drawings

A practical application of our neural network is the automatic conversion of hand drawings into a subset of LaTeX. We train the model to generalize to hand drawings by introducing noise into the renderings of the training target images. We designed this noise process to introduce the kinds of variations found in hand drawings (Fig. 5; see supplement for details).



Figure 5: (a): hand drawing. (b): Rendering of the trace set our model infers for (a). (c): noisy rendering of (b).

Our neurally-guided SMC procedure used pixel-wise distance as a surrogate for a likelihood function ($L(\cdot|\cdot)$ in section 2). But pixel-wise distance fares poorly on hand drawings, which never exactly match the model's renders. So, for hand drawings, we *learn* a surrogate likelihood function, $L_{\text{learned}}(\cdot|\cdot)$. The density $L_{\text{learned}}(\cdot|\cdot)$ is predicted by a convolutional network that we train to predict the distance between two traces conditioned upon their renderings. We train our likelihood surrogate to approximate the symmetric difference, which is the number of drawing commands by which two traces differ:

$$-\log L_{\text{learned}}(\text{render}(T_1)|\text{render}(T_2)) \approx |T_1 - T_2| + |T_2 - T_1| \tag{1}$$

Pixel-wise distance metrics are sensitive to the details of how arrows, dashes, and corners are drawn – but we wish to be invariant to these details. So, we learn a distance metric over images that approximates the distance metric in the search space over traces.

We evaluate our system on 100 hand-drawn figures; see Fig. 6–7. These were drawn carefully but not perfectly. Because our model assumes that objects are snapped to a 16×16 grid, we made the drawings on graph paper. For each drawing we annotated a ground truth trace set and have the

neurally guided SMC sampler produce many candidate traces for each drawing. For 63% of the drawings, the Top-1 most likely sample exactly matches the ground truth; with more samples, the model finds traces that are closer to the ground truth annotation (Fig. 8). We will show that the program synthesizer corrects some of these small errors (Sec. 4.1).



Figure 6: Left to right: Ising model, recurrent network architecture, figure from a deep learning textbook Goodfellow et al. (2016), graphical model



Figure 7: Near misses. Rightmost: illusory contours (note: no SMC)



Figure 8: How close are the model's outputs to the ground truth on hand drawings, as we consider larger sets of samples (1, 5, 100)? Distance to ground truth trace measured by the intersection over union of predicted vs. ground truth traces. (a) for 63% of drawings the model's top prediction is exactly correct; (b) for 70% of drawings the ground truth is in the top 5 model predictions; (c) for 4% of drawings all of the model outputs have no overlap with the ground truth trace. Red: the full model. Other colors: lesioned versions of our model.

3 SYNTHESIZING GRAPHICS PROGRAMS FROM TRACE SETS

Although the trace set of a graphics program describes the contents of a scene, it does not encode higher-level features of the image, such as repeated motifs or symmetries. A *graphics program* better describes such structures. We seek to synthesize graphics programs from their traces.

We constrain the space of allowed programs by writing down a context free grammar over a space of programs. Although it might be desirable to synthesize programs in a Turing-complete language such as Lisp or Python, a more tractable approach is to specify what in the program languages community is called a Domain Specific Language (DSL) Polozov & Gulwani (2015). Our DSL (Tbl. 2) encodes prior knowledge of what graphics programs tend to look like.

Table 2: Grammar over graphics programs. We allow loops (`for`) with conditionals (`if`), vertical/horizontal reflections (`reflect`), variables (Var) and affine transformations ($\mathbb{Z}\times$Var+$\mathbb{Z}$).

Program→	Statement; $\cdots$; Statement
Statement→	`circle`(Expression,Expression)
Statement→	`rectangle`(Expression,Expression,Expression,Expression)
Statement→	`line`(Expression,Expression,Expression,Expression,Boolean,Boolean)
Statement→	`for`($0 \leq$ Var $<$ Expression) `{ if` (Var > 0) `{` Program `}; Program }`
Statement→	`reflect`(Axis) `{` Program `}`
Expression→	$\mathbb{Z}\times$Var+$\mathbb{Z}$
Var→	A free (unused) variable
$\mathbb{Z}$ →	an integer
Axis→	`X = `$\mathbb{Z}$ `| Y = `$\mathbb{Z}$

Given the DSL and a trace T, we want to recover a program that both evaluates to T and, at the same time, is the "best" explanation of T. For example, we might prefer more general programs or, in the spirit of Occam's razor, prefer shorter programs. We wrap these intuitions up into a cost function over programs, and seek the minimum cost program consistent with T:

$$\text{program}(T) = \underset{p \in \text{DSL, s.t. } p \text{ evaluates to } T}{\arg\min} \text{cost}(p) \tag{2}$$

We define the cost of a program to be the number of Statement's it contains (Tbl. 2). We also penalize using many different numerical constants; see supplement.

The constrained optimization problem in Eq. 2 is intractable in general, but there exist efficient-in-practice tools for finding exact solutions to such program synthesis problems. We use the state-of-the-art Sketch tool Solar Lezama (2008). Sketch takes as input a space of programs, along with a specification of the program's behavior and optionally a cost function. It translates the synthesis problem into a constraint satisfaction problem and then uses a SAT solver to find a minimum-cost program satisfying the specification. Sketch requires a *finite program space*, which here means that the depth of the program syntax tree is bounded (we set the bound to 3), but has the guarantee that it always eventually finds the globally optimal solution. In exchange for this optimality guarantee it comes with no guarantees on runtime. For our domain synthesis times vary from minutes to hours, with 27% of the drawings timing out the synthesizer after 1 hour. Fig. 9 shows programs recovered by our system. A main impediment to our use of these general techniques is the prohibitively high cost of searching for programs. We next describe how to learn to synthesize programs much faster (Sec. 3.1), timing out on 2% of the drawings and solving 58% of problems within a minute.

3.1 Learning a search policy for synthesizing programs

We want to leverage powerful, domain-general techniques from the program synthesis community, but make them much faster by learning a domain-specific *search policy*. A search policy proposes search problems like those in Eq. 2, but also offers additional constraints on the structure of the program (Tbl. 3). For example, a policy might decide to first try searching over small programs before searching over large programs, or decide to prioritize searching over programs that have loops.

A search policy $\pi_\theta(\sigma|T)$ takes as input a trace T and predicts a distribution over synthesis problems, each of which is written σ and corresponds to a set of possible programs to search over (so $\sigma \subset$ DSL). Good policies will prefer tractable program spaces, so that the search procedure will terminate early, but should also prefer program spaces likely to contain programs that concisely explain the data. These two desiderata are in tension: tractable synthesis problems involve searching over smaller spaces, but smaller spaces are less likely to contain a minimum cost program for explaining the trace. Our goal now is to find the parameters of the policy, written θ, which best navigate this trade-off.

Given a search policy, what is the best way of using it to quickly find minimum cost programs? We use a *bias-optimal search algorithm* (Schmidhuber, 2004):

Definition: Bias-optimality. A search algorithm is *n-bias optimal* with respect to a distribution $\mathbb{P}_{\text{bias}}[\cdot]$ if it is guaranteed to find a solution in σ after searching for at least time $n \times \frac{t(\sigma)}{\mathbb{P}_{\text{bias}}[\sigma]}$, where $t(\sigma)$ is the time it takes to verify that σ contains a solution to the search problem.

Drawing	Trace Set	Program	Compression factor

	`Line(2,15, 4,15)`
	`Line(4,9, 4,13)`
	`Line(3,11, 3,14)`
	`Line(2,13, 2,15)`
	`Line(3,14, 6,14)`
	`Line(4,13, 8,13)`
		`for(i<3)`
		` line(i,-1*i+6,`
		`  2*i+2,-1*i+6)`
		` line(i,-2*i+4,i,-1*i+6)`
			$\frac{6}{3} = 2\text{x}$

	`Line(5,13,2,10,arrow)`
	`Circle(5,9)`
	`Circle(8,5)`
	`Line(2,8, 2,6,arrow)`
	`Circle(2,5)`
	... etc. ...; 13 lines
		`circle(4,10)`
		`for(i<3)`
		` circle(-3*i+7,5)`
		` circle(-3*i+7,1)`
		` line(-3*i+7,4,-3*i+7,2,arrow)`
		` line(4,9,-3*i+7,6,arrow)`
			$\frac{13}{6} = 2.2\text{x}$

	`Circle(5,8)`
	`Circle(2,8)`
	`Circle(8,11)`
	`Line(2,9, 2,10)`
	`Circle(8,8)`
	`Line(3,8, 4,8)`
	`Line(3,11, 4,11)`
	... etc. ...; 21 lines
		`for(i<3)`
		` for(j<3)`
		`  if(j>0)`
		`  line(-3*j+8,-3*i+7,`
		`  -3*j+9,-3*i+7)`
		`  line(-3*i+7,-3*j+8,`
		`  -3*i+7,-3*j+9)`
		`  circle(-3*j+7,-3*i+7)`
			$\frac{21}{6} = 3.5\text{x}$

	`Rectangle(1,10,3,11)`
	`Rectangle(1,12,3,13)`
	`Rectangle(4,8,6,9)`
	`Rectangle(4,10,6,11)`
	... etc. ...; 16 lines
		`for(i<4)`
		` for(j<4)`
		`  rectangle(-3*i+9,-2*j+6,`
		`  -3*i+11,-2*j+7)`
			$\frac{16}{3} = 5.3\text{x}$

	`Line(11,14,13,14,arrow)`
	`Circle(10,10)`
	`Line(10,13,10,11,arrow)`
	`Circle(6,10)`
	... etc. ...; 15 lines
		`for(i<4)`
		` line(-4*i+13,4,-4*i+13,2,arrow)`
		` for(j<3)`
		`  if(j>0)`
		`  circle(-4*i+13,4*j+-3)`
		`  line(-4*j+10,5,-4*j+12,5,`
		`  arrow)`
			$\frac{15}{6} = 2.5\text{x}$

	`Line(3,10,3,14,arrow)`
	`Rectangle(11,8,15,10)`
	`Rectangle(11,14,15,15)`
	`Line(13,10,13,14,arrow)`
	... etc. ...; 16 lines
		`for(i<3)`
		` line(7,1,5*i+2,3,arrow)`
		` for(j<i+1)`
		`  if(j>0)`
		`  line(5*j-1,9,5*i,5,arrow)`
		`  line(5*j+2,5,5*j+2,9,arrow)`
		` rectangle(5*i,3,5*i+4,5)`
		` rectangle(5*i,9,5*i+4,10)`
		`rectangle(2,0,12,1)`
			$\frac{16}{9} = 1.8\text{x}$

	`Circle(2,8)`
	`Rectangle(6,9, 7,10)`
	`Circle(8,8)`
	`Rectangle(6,12, 7,13)`
	`Rectangle(3,9, 4,10)`
	... etc. ...; 9 lines
		`reflect(y=8)`
		` for(i<3)`
		`  if(i>0)`
		`  rectangle(3*i-1,2,3*i,3)`
		`  circle(3*i+1,3*i+1)`
			$\frac{9}{5} = 1.8\text{x}$

Figure 9: Example drawings (left), their ground truth trace sets (middle left), and programs synthesized from these traces (middle right). Compared to the trace the programs are more compressive (right: programs have fewer lines than traces) and automatically group together related drawing commands. Note the nested loops in the Ising model, special case conditionals for the HMM, combination of symmetry and iteration in the bottom figure, affine transformations in the top figure, and the complicated program in the second figure to bottom.

Intuitively, an n-bias optimal search algorithm spends at least $\mathbb{P}_{\text{bias}}[\sigma]/n$ of its time exploring solution space σ. An example of a 1-bias optimal search algorithm is a time-sharing system that allocates $\mathbb{P}_{\text{bias}}[\sigma]$ of its time to trying σ. We construct a 1-bias optimal search algorithm for our domain by

identifying $\mathbb{P}_{\text{bias}}[\sigma] = \pi_\theta(\sigma|T)$ and $t(\sigma)$ with how long the synthesizer takes to search the programs in σ. This means that the search algorithm explores the entire program space, but spends most of its time searching through the regions of the space that the policy judges to be most promising.

Now in theory any $\pi_\theta(\cdot|\cdot)$ is a bias-optimal searcher. But the actual runtime of the algorithm depends strongly upon the bias $\mathbb{P}_{\text{bias}}[\cdot]$. Our new approach is to learn $\mathbb{P}_{\text{bias}}[\cdot]$ by picking the policy minimizing the expected bias-optimal time to solve a training corpus, $\mathcal{D}$, of graphics program synthesis problems:

$$\text{Loss}(\theta; \mathcal{D}) = \mathbb{E}_{T\sim\mathcal{D}}\left[\min_{\sigma\in\text{Best}(T)} \frac{t(\sigma|T)}{\pi_\theta(\sigma|T)}\right] + \lambda\|\theta\|_2^2 \tag{3}$$

where $\sigma \in \text{Best}(T)$ if a minimum cost program for T is in σ.

To generate a training corpus for learning a policy which minimizes this loss, we synthesized minimum cost programs for each trace of our hand drawings and for each σ. We locally minimize this loss using gradient descent. See supplement for details. Because we want to learn a policy from only 100 hand-drawn sketches, we chose a simple low-capacity, bilinear model for a policy:

$$\pi_\theta(\sigma|T) \propto \exp\left(\phi_{\text{params}}(\sigma)^\top \theta \phi_{\text{trace}}(T)\right) \tag{4}$$

where $\phi_{\text{params}}(\sigma)$ is a one-hot encoding of the parameter settings of σ (see Tbl. 3) and $\phi_{\text{trace}}(T)$ extracts a few simple features of the trace T; see supplement for details.

We contrast our learned search policy with two alternatives (see Fig. 10): (1) *Sketch*, which poses the entire problem wholesale to the Sketch program synthesizer; and (2) an *Oracle*, a policy which always picks the quickest to search σ also containing a minimum cost program. Our approach improves upon Sketch by itself, and comes close to the Oracle's performance. One could never construct this Oracle, because the agent does not know ahead of time which σ's contain minimum cost programs nor does it know how long each σ will take to search. The Oracle is an upper bound on the performance of any search policy. With this learned policy in hand we can synthesize 58% of programs within a minute.

Table 3: Parameterization of different ways of posing the program synthesis problem. The policy learns to choose parameters likely to quickly yield a minimal cost program. We slightly abuse notation by writing σ to mean an assignment to each of these parameters (so σ assumes one of 24 different values) and to mean the set of programs selected by that parameterization (so $\sigma \subseteq$ DSL)

Parameter	Description	Range
Loops?	Is the program allowed to loop?	$\{\text{True}, \text{False}\}$
Reflects?	Is the program allowed to have reflections?	$\{\text{True}, \text{False}\}$
Incremental?	Solve the problem piece-by-piece or all at once?	$\{\text{True}, \text{False}\}$
Maximum depth	Bound on the depth of the program syntax tree	$\{1, 2, 3\}$



Figure 10: How long does it typically take to synthesize a minimum cost program? Sketch: out-of-the-box performance of the Sketch (Solar Lezama, 2008) program synthesizer. Oracle: baseline that picks the easiest synthesis problem containing a minimum cost program. Learned policy: a bias-optimal learned search policy running on an ideal timesharing machine. Oracle upper bounds the performance of any search policy. ∞ = timeout. Red dashed line is median time. Learned policy evaluated using 20-fold cross validation.

4 APPLICATIONS OF GRAPHICS PROGRAM SYNTHESIS

Why synthesize a graphics program, if the trace already suffices to recover the objects in an image? Within our domain of hand-drawn figures, graphics program synthesis has several uses:

4.1 CORRECTING ERRORS MADE BY THE NEURAL NETWORK

The program synthesizer corrects errors made by the neural network by favoring trace sets which lead to more concise or general programs. For example, figures with perfectly aligned objects are preferable to figures whose parts are slightly misaligned, and precise alignment lends itself to short programs. Concretely, we run the program synthesizer on the Top-k most likely traces output by the neurally guided sampler. Then, the system reranks the Top-k by the prior probability of their programs. The prior probability of a program is learned by picking the prior maximizing the likelihood of the ground truth trace sets; see supplement for details.



Figure 11: Left: hand drawings. Center: interpretations favored by the deep network. Right: interpretations favored after learning a prior over programs. Our learned prior favors shorter, simpler programs, thus (top example) continuing the pattern of not having an arrow is preferred, or (bottom example) continuing the "binary search tree" is preferred.

This procedure can only fix mistakes made by the neural network when a correct trace is in the Top-k. Our sampler could only do better on 7/100 drawings by looking at the Top-5 or Top-100 sampled traces (see Fig. 8), precluding a statistically significant analysis of how much learning a prior over programs could help correct errors. But, learning this prior does sometimes help correct mistakes made by the neural network, and also occasionally introduces mistakes of its own; see Fig. 11 for a representative example of the kinds of corrections that it makes. See supplement for details.

4.2 MODELING SIMILARITY BETWEEN DRAWINGS

Modeling drawings using programs opens up new ways to measure similarity between them. For example, we might say that two drawings are similar if they both contain loops of length 4, or if they share a reflectional symmetry, or if they are both organized according to a grid-like structure.

We measure the similarity between two drawings by extracting features of the lowest-cost programs that describe them. Our features are counts of the number of times that different components in the DSL were used (Tbl. 2). We then find drawings which are either close together or far apart in program feature space. One could use many alternative similarity metrics between drawings which would capture pixel-level similarities while missing high-level geometric similarities. We used our learned distance metric between trace sets, $L_{\text{learned}}(\cdot|\cdot)$, to find drawings that are either close together or far apart according to the learned distance metric over images. Fig. 12 illustrates the kinds of drawings that these different metrics put closely together, while the supplement shows low dimensional projections of program and image features.

4.3 EXTRAPOLATING FIGURES

Having access to the source code of a graphics program facilitates coherent, high-level edits to the figure generated by that program. For example, we could change all of the circles to squares or make all of the lines be dashed. We extrapolate figures by increasing the number of times that loops are executed. Extrapolating repetitive visuals patterns comes naturally to humans, and building this ability into an application is practical: imagine hand drawing a repetitive graphical model structure and having our system automatically induce and extend the pattern. Fig. 13 shows extrapolations produced by our system.



Figure 12: Pairs of images either close together or far apart in different features spaces. The symbol $\leftrightarrow$ points to the compared images. Features of the program capture abstract notions like symmetry and repetition. Distance metric over images is $L_{\text{learned}}(\cdot|\cdot)$ (see Section 2.1). The off-diagonal entries highlight the difference between these metrics: similarity of programs captures high-level features like repetition and symmetry, whereas similarity of images correspondends to similar drawing commands being in similar places. See Section 2 of the supplement for more examples.



Figure 13: Top, white: hand drawings. Bottom, black: extrapolations produced by running loops for extra iterations.

5 RELATED WORK

Program Induction: Our approach to learning to search for programs draws theoretical underpinnings from Levin search (Levin, 1973; Solomonoff, 1984) and Schmidhuber's OOPS model (Schmidhuber, 2004). DeepCoder (Balog et al., 2016) is a recent model which, like ours, learns to predict likely program components. Our work differs because we treat the problem as *metareasoning*, identifying and modeling the trade-off between tractability and probability of success. TerpreT (Gaunt et al., 2016) systematically compares constraint-based program synthesis techniques against gradient-based search techniques, like those used to train Differentiable Neural Computers (Graves et al., 2016). The TerpreT experiments motivate our use of constraint-based techniques.

Deep Learning: Our neural network bears resemblance to the Attend-Infer-Repeat (AIR) system, which learns to decompose an image into its constituent objects (Eslami et al., 2016). AIR learns an iterative inference scheme which infers objects one by one and also decides when to stop inference. Our network differs in its architecture and training regime: AIR learns a recurrent auto-encoding model via variational inference, whereas our parsing stage learns an autoregressive-style model from randomly-generated (trace, image) pairs.

IM2LATEX (Deng et al., 2017) is a recent work that also converts images to LaTeX. Their goal is to derender LaTeX equations, which recovers a markup language representation. Our goal is to go from noisy input to a high-level program, which goes beyond markup languages by supporting programming constructs like loops and conditionals. Recovering a high-level program is more challenging than recovering markup because it is a highly under constrained symbolic reasoning problem.

Our image-to-trace parsing architecture builds on prior work on controlling procedural graphics programs (Ritchie et al., 2016). We adapt this method to a different visual domain (figures composed of multiple objects), using a broad prior over possible scenes as the initial program and viewing the trace through the guide program as a symbolic parse of the target image. We then show how to efficiently synthesize higher-level programs from these traces.

In the computer graphics literature, there have been other systems which convert sketches into procedural representations. One uses a convolutional network to match a sketch to the output of a parametric 3D modeling system (Huang et al., 2017). Another uses convolutional networks to support sketch-based instantiation of procedural primitives within an interactive architectural modeling system (Nishida et al., 2016). Both systems focus on inferring fixed-dimensional parameter vectors. In contrast, we seek to automatically infer a structured, programmatic representation of a sketch which captures higher-level visual patterns.

Hand-drawn sketches: Prior work has also applied sketch-based program synthesis to authoring graphics programs. Sketch-n-Sketch is a bi-directional editing system in which direct manipulations to a program's output automatically propagate to the program source code (Hempel & Chugh, 2016). We see this work as complementary to our own: programs produced by our method could be provided to a Sketch-n-Sketch-like system as a starting point for further editing. The CogSketch system (Forbus et al., 2011) also aims to have a high-level understanding of hand-drawn figures. Their primary goal is cognitive modeling (they apply their system to solving IQ-test style visual reasoning problems), whereas we are interested in building an automated AI application (e.g. in our system the user need not annotate which strokes correspond to which shapes; our neural network produces something equivalent to the annotations).

The Trace Hypothesis: The idea that an execution trace could assist in program learning goes back to the 1970's (Summers, 1977) and has been applied in neural models of program induction, like Neural Program Interpreters (Reed & de Freitas, 2015), or DeepCoder, which predicts what functions occur in the execution trace (Balog et al., 2016). Our contribution to this idea is the trace hypothesis: that trace sets can be inferred from perceptual data, and that the trace is the correct bridge between perception and symbolic representation. Our work is the first to articulate and explore this hypothesis by demonstrating how a trace could be inferred and how it can be used to synthesize a high-level program.

6 CONTRIBUTIONS

We have presented a system for inferring graphics programs which generate LaTeX-style figures from hand-drawn images. The system uses a combination of deep neural networks and stochastic search to parse drawings into symbolic trace sets; it then feeds these traces to a general-purpose program synthesis engine to infer a structured graphics program. We evaluated our model's performance at parsing novel images, and we demonstrated its ability to extrapolate from provided drawings and to organize them according to high-level geometric features.

In the near future, we believe it will be possible to produce professional-looking figures just by drawing them and then letting an artificially-intelligent agent write the code. More generally, we believe the trace hypothesis, as realized in our two-phase system—parsing into trace sets, then searching for a low-cost symbolic program which generates those traces—may be a useful paradigm for other domains in which agents must programmatically reason about noisy perceptual input.

REFERENCES

Martín Abadi, Ashish Agarwal, Paul Barham, Eugene Brevdo, Zhifeng Chen, Craig Citro, Greg S. Corrado, Andy Davis, Jeffrey Dean, Matthieu Devin, Sanjay Ghemawat, Ian Goodfellow, Andrew Harp, Geoffrey Irving, Michael Isard, Yangqing Jia, Rafal Jozefowicz, Lukasz Kaiser, Manjunath Kudlur, Josh Levenberg, Dan Mané, Rajat Monga, Sherry Moore, Derek Murray, Chris Olah, Mike Schuster, Jonathon Shlens, Benoit Steiner, Ilya Sutskever, Kunal Talwar, Paul Tucker, Vincent Vanhoucke, Vijay Vasudevan, Fernanda Viégas, Oriol Vinyals, Pete Warden, Martin Wattenberg, Martin Wicke, Yuan Yu, and Xiaoqiang Zheng. TensorFlow: Large-scale machine learning on heterogeneous systems, 2015. URL `http://tensorflow.org/`. Software available from tensorflow.org.

Matej Balog, Alexander L. Gaunt, Marc Brockschmidt, Sebastian Nowozin, and Daniel Tarlow. DeepCoder: Learning to write programs. *arXiv preprint arXiv:1611.01989*, November 2016. URL `https://arxiv.org/abs/1611.01989`.

Tony Beltramelli. pix2code: Generating code from a graphical user interface screenshot. *CoRR*, abs/1705.07962, 2017. URL `http://arxiv.org/abs/1705.07962`.

Yuntian Deng, Anssi Kanervisto, Jeffrey Ling, and Alexander M. Rush. Image-to-markup generation with coarse-to-fine attention. In *ICML*, 2017.

Arnaud Doucet, Nando De Freitas, and Neil Gordon (eds.). *Sequential Monte Carlo Methods in Practice*. Springer, 2001.

SM Eslami, N Heess, and T Weber. Attend, infer, repeat: Fast scene understanding with generative models. arxiv preprint arxiv:..., 2016. 2016.

Kenneth Forbus, Jeffrey Usher, Andrew Lovett, Kate Lockwood, and Jon Wetzel. Cogsketch: Sketch understanding for cognitive science research and for education. *Topics in Cognitive Science*, 3(4):648–666, 2011.

Alexander L Gaunt, Marc Brockschmidt, Rishabh Singh, Nate Kushman, Pushmeet Kohli, Jonathan Taylor, and Daniel Tarlow. Terpret: A probabilistic programming language for program induction. *arXiv preprint arXiv:1608.04428*, 2016.

Ian Goodfellow, Yoshua Bengio, and Aaron Courville. *Deep Learning*. MIT Press, 2016. `http://www.deeplearningbook.org`.

Alex Graves, Greg Wayne, Malcolm Reynolds, Tim Harley, Ivo Danihelka, Agnieszka Grabska-Barwińska, Sergio Gómez Colmenarejo, Edward Grefenstette, Tiago Ramalho, John Agapiou, et al. Hybrid computing using a neural network with dynamic external memory. *Nature*, 538(7626):471–476, 2016.

Brian Hempel and Ravi Chugh. Semi-automated svg programming via direct manipulation. In *Proceedings of the 29th Annual Symposium on User Interface Software and Technology*, UIST '16, pp. 379–390, New York, NY, USA, 2016. ACM. ISBN 978-1-4503-4189-9. doi: 10.1145/2984511.2984575. URL `http://doi.acm.org/10.1145/2984511.2984575`.

Haibin Huang, Evangelos Kalogerakis, Ersin Yumer, and Radomir Mech. Shape synthesis from sketches via procedural models and convolutional networks. *IEEE transactions on visualization and computer graphics*, 2017.

Max Jaderberg, Karen Simonyan, Andrew Zisserman, et al. Spatial transformer networks. In *Advances in Neural Information Processing Systems*, pp. 2017–2025, 2015.

Leonid Anatolevich Levin. Universal sequential search problems. *Problemy Peredachi Informatsii*, 9(3):115–116, 1973.

Gen Nishida, Ignacio Garcia-Dorado, Daniel G. Aliaga, Bedrich Benes, and Adrien Bousseau. Interactive sketching of urban procedural models. *ACM Trans. Graph.*, 35(4), 2016.

Oleksandr Polozov and Sumit Gulwani. Flashmeta: A framework for inductive program synthesis. *ACM SIGPLAN Notices*, 50(10):107–126, 2015.

Scott Reed and Nando de Freitas. Neural programmer-interpreters. *CoRR*, abs/1511.06279, 2015. URL http://arxiv.org/abs/1511.06279.

Daniel Ritchie, Anna Thomas, Pat Hanrahan, and Noah Goodman. Neurally-guided procedural models: Amortized inference for procedural graphics programs using neural networks. In *Advances In Neural Information Processing Systems*, pp. 622–630, 2016.

Jürgen Schmidhuber. Optimal ordered problem solver. *Machine Learning*, 54(3):211–254, 2004.

Armando Solar Lezama. *Program Synthesis By Sketching*. PhD thesis, EECS Department, University of California, Berkeley, Dec 2008. URL http://www.eecs.berkeley.edu/Pubs/TechRpts/2008/EECS-2008-177.html.

Raymond J Solomonoff. Optimum sequential search. 1984.

Phillip D. Summers. A methodology for lisp program construction from examples. *J. ACM*, 24(1):161–175, January 1977. ISSN 0004-5411. doi: 10.1145/321992.322002. URL http://doi.acm.org/10.1145/321992.322002.

Oriol Vinyals, Alexander Toshev, Samy Bengio, and Dumitru Erhan. Show and tell: A neural image caption generator. In *Proceedings of the IEEE conference on computer vision and pattern recognition*, pp. 3156–3164, 2015.

Jiajun Wu, Joshua B Tenenbaum, and Pushmeet Kohli. Neural scene de-rendering. In *IEEE Conference on Computer Vision and Pattern Recognition (CVPR)*, 2017.

SUPPLEMENT TO: LEARNING TO INFER GRAPHICS PROGRAMS FROM HAND-DRAWN IMAGES

Anonymous authors
Paper under double-blind review

1 CORRECTING ERRORS MADE BY THE NEURAL NETWORK

The program synthesizer can help correct errors from the execution trace proposal network by favoring execution traces which lead to more concise or general programs. For example, one generally prefers figures with perfectly aligned objects over figures whose parts are slightly misaligned – and precise alignment lends itself to short programs. Similarly, figures often have repeated parts, which the program synthesizer might be able to model as a loop or reflectional symmetry. So, in considering several candidate traces proposed by the neural network, we might prefer traces whose best programs have desirable features such being short or having iterated structures.

Concretely, we implemented the following scheme: for an image I, the neurally guided sampling scheme of section 3 of the main paper samples a set of candidate traces, written $\mathcal{F}(I)$. Instead of predicting the most likely trace in $\mathcal{F}(I)$ according to the neural network, we can take into account the programs that best explain the traces. Writing $\hat{T}(I)$ for the trace the model predicts for image I,

$$\hat{T}(I) = \arg\max_{T \in \mathcal{F}(I)} L_{\text{learned}}(I|\text{render}(T)) \times \mathbb{P}_\theta[T|I] \times \mathbb{P}_\beta[\text{program}(T)] \tag{1}$$

where $\mathbb{P}_\beta[\cdot]$ is a prior probability distribution over programs parameterized by β. This is equivalent to doing MAP inference in a generative model where the program is first drawn from $\mathbb{P}_\beta[\cdot]$, then the program is executed deterministically, and then we observe a noisy version of the program's output, where $L_{\text{learned}}(I|\text{render}(\cdot)) \times \mathbb{P}_\theta[\cdot|I]$ is our observation model.

Given a corpus of graphics program synthesis problems with annotated ground truth traces (i.e. (I, T) pairs), we find a maximum likelihood estimate of β:

$$\beta^* = \arg\max_\beta \mathbb{E}\left[\log \frac{\mathbb{P}_\beta[\text{program}(T)] \times L_{\text{learned}}(I|\text{render}(T)) \times \mathbb{P}_\theta[T|I]}{\sum_{T' \in \mathcal{F}(I)} \mathbb{P}_\beta[\text{program}(T')] \times L_{\text{learned}}(I|\text{render}(T')) \times \mathbb{P}_\theta[T'|I]}\right] \tag{2}$$

where the expectation is taken both over the model predictions and the (I, T) pairs in the training corpus. We define $\mathbb{P}_\beta[\cdot]$ to be a log linear distribution $\propto \exp(\beta \cdot \phi(\text{program}))$, where $\phi(\cdot)$ is a feature extractor for programs. We extract a few basic features of a program, such as its size and how many loops it has, and use these features to help predict whether a trace is the correct explanation for an image.

We synthesized programs for the top 10 traces output by the deep network. Learning this prior over programs can help correct mistakes made by the neural network, and also occasionally introduces mistakes of its own; see Fig. 1 for a representative example of the kinds of corrections that it makes. On the whole it modestly improves our Top-1 accuracy from 63% to 67%. Recall that from Fig. 6 of the main paper that the best improvement in accuracy we could possibly get is 70% by looking at the top 10 traces.



Figure 1: Left: hand drawing. Center: interpretation favored by the deep network. Right: interpretation favored after learning a prior over programs. Our learned prior favors shorter, simpler programs, thus (top example) continuing the pattern of not having an arrow is preferred, or (bottom example) continuing the binary search tree is preferred.

2 MEASURING SIMILARITY BETWEEN DRAWINGS

We measure the similarity between two drawings by extracting features of the best programs that describe them. Our features are counts of the number of times that different components in the DSL were used. We project these features down to a 2-dimensional subspace using primary component analysis (PCA); see Fig.2. One could use many alternative similarity metrics between drawings which would capture pixel-level similarities while missing high-level geometric similarities. We used our learned distance metric between traces, $L_{\text{learned}}(\cdot|\cdot)$, and projected to a 2-dimensional subspace using multidimensional scaling (MDS: (1)). This reveals similarities between the objects in the drawings, while missing similarities at the level of the program.

3 LEARNING A BIAS OPTIMAL POLICY

Recall from the main paper that our goal is to estimate the policy minimizing the following loss:

$$\textsc{Loss}(\theta;\mathcal{D}) = \mathbb{E}_{T\sim\mathcal{D}}\left[\min_{\sigma\in\textsc{Best}(T)} \frac{t(\sigma|T)}{\pi_\theta(\sigma|T)}\right] + \lambda\|\theta\|_2^2 \tag{3}$$

where $\sigma \in \textsc{Best}(T)$ if a minimum cost program for T is in σ.

We make this optimization problem tractable by annealing our loss function during gradient descent:

$$\textsc{Loss}_\beta(\theta;\mathcal{D}) = \mathbb{E}_{T\sim\mathcal{D}}\left[\textsc{SoftMinimum}_\beta\left\{\frac{t(\sigma|T)}{\pi_\theta(\sigma|T)} : \sigma\in\textsc{Best}(T)\right\}\right] + \lambda\|\theta\|_2^2 \tag{4}$$

$$\text{where } \textsc{SoftMinimum}_\beta(x_1,x_2,x_3,\cdots) = \sum_n x_n \frac{e^{-\beta x_n}}{\sum_{n'} e^{-\beta x_{n'}}} \tag{5}$$

Notice that $\textsc{SoftMinimum}_{\beta=\infty}(\cdot)$ is just $\min(\cdot)$. We set the regularization coefficient $\lambda = 0.1$ and minimize equation 4 using Adam for 2000 steps, linearly increasing β from 1 to 2.

We parameterize the space of policies as a simple log bilinear model:

$$\pi_\theta(\sigma|T) \propto \exp\left(\phi_{\text{params}}(\sigma)^\top\theta\phi_{\text{trace}}(T)\right) \tag{6}$$

where:

$$\begin{aligned}\phi_{\text{params}}(\sigma) = [&\mathbb{1}[\sigma \text{ can loop}];\\ &\mathbb{1}[\sigma \text{ can reflect}];\\ &\mathbb{1}[\sigma \text{ is incremental}];\\ &\mathbb{1}[\sigma \text{ has depth bound } 1];\mathbb{1}[\sigma \text{ has depth bound } 2];\mathbb{1}[\sigma \text{ has depth bound } 3];]\\ \phi_{\text{trace}}(T) = [&\#\text{ circles in } T;\#\text{ rectangles in } T;\#\text{ lines in } T;1]\end{aligned}$$



Figure 2: PCA on features of the programs that were synthesized for each drawing. Symmetric figures cluster to the right; "loopy" figures cluster to the left; complicated programs are at the top and simple programs are at the bottom.



Figure 3: MDS on drawings using the learned distance metric, $L_{\text{learned}}(\cdot|\cdot)$. Drawings with similar looking parts in similar locations are clustered together.

4 NEURAL NETWORK ARCHITECTURE

4.1 HIGH-LEVEL OVERVIEW

For the model in Fig. 4, the distribution over the next drawing command factorizes as:

$$\mathbb{P}_\theta[t_1 t_2 \cdots t_K | I, T] = \prod_{k=1}^{K} \mathbb{P}_\theta \left[t_k | a_\theta \left(f_\theta(I, \text{render}(T)) | \{t_j\}_{j=1}^{k-1} \right), \{t_j\}_{j=1}^{k-1} \right] \tag{7}$$

where $t_1 t_2 \cdots t_K$ are the tokens in the drawing command, I is the target image, T is a trace set, θ are the parameters of the neural network, $f_\theta(\cdot, \cdot)$ is the image feature extractor (convolutional network),



Figure 4: Our neural architecture for inferring the trace set of a graphics program from its output. Blue: network inputs. Black: network operations. Red: samples from a multinomial. `Typewriter font`: network outputs. Renders snapped to a 16×16 grid, illustrated in gray. STN (spatial transformer network) is a differentiable attention mechanism (2).

and $a_\theta(\cdot|\cdot)$ is an attention mechanism. The distribution over traces factorizes as:

$$\mathbb{P}_\theta[T|I] = \prod_{n=1}^{|T|} \mathbb{P}_\theta[T_n|I, T_{1:(n-1)}] \times \mathbb{P}_\theta[\texttt{STOP}|I, T] \tag{8}$$

where $|T|$ is the length of trace T, the subscripts on T index drawing commands within the trace (so T_n is a sequence of tokens: $t_1 t_2 \cdots t_K$), and the `STOP` token is emitted by the network to signal that the trace explains the image.

4.2 Convolutional Network

The convolutional network takes as input 2 256×256 images represented as a $2 \times 256 \times 256$ volume. These are passed through two layers of convolutions separated by ReLU nonlinearities and max pooling:

- Layer 1: 20 8×8 convolutions, 2 16×4 convolutions, 2 4×16 convolutions. Followed by 8×8 pooling with a stride size of 4.
- Layer 2: 10 8×8 convolutions. Followed by 4×4 pooling with a stride size of 4.

4.3 Autoregressive Decoding of Drawing Commands

Given the image features f, we predict the first token (i.e., the name of the drawing command: `circle`, `rectangle`, `line`, or `STOP`) using logistic regression:

$$\mathbb{P}[t_1] \propto \exp\left(W_{t_1} f + b_{t_1}\right) \tag{9}$$

where W_{t_1} is a learned weight matrix and b_{t_1} is a learned bias vector.

Given an attention mechanism $a(\cdot|\cdot)$, subsequent tokens are predicted as:

$$\mathbb{P}[t_n|t_{1:(n-1)}] \propto \text{MLP}_{t_1,n}(a(f|t_{1:(n-1)}) \oplus \bigoplus_{j<n} \text{oneHot}(t_j)) \tag{10}$$

Thus each token of each drawing primitive has its own learned MLP. For predicting the coordinates of lines we found that using 32 hidden nodes with sigmoid activations worked well; for other tokens the MLP's are just logistic regression (no hidden nodes).

We use Spatial Transformer Networks (2) as our attention mechanism. The parameters of the spatial transform are predicted on the basis of previously predicted tokens. For example, in order to decide where to focus our attention when predicting the y coordinate of a circle, we condition upon both the identity of the drawing command (`circle`) and upon the value of the previously predicted x coordinate:

$$a(f|t_{1:(n-1)}) = \text{AffineTransform}(f, \text{MLP}_{t_1,n}(\bigoplus_{j<n} \text{oneHot}(t_j))) \tag{11}$$

So, we learn a different network for predicting special transforms *for each drawing command* (value of t_1) and also *for each token of the drawing command*. These networks ($\text{MLP}_{t_1,n}$ in equation 11) have no hidden layers and output the 6 entries of an affine transformation matrix; see (2) for more details.

Training takes a little bit less than a day on a Nvidia TitanX GPU. The network was trained on 10^5 synthetic examples.

4.4 Predicting continuous coordinates using Mixture Density Networks

Our main paper describes a neural model for parsing hand drawings into LaTeX, but comes with the restriction that all of the coordinates of all the drawing commands are snapped to a 16×16 grid. Now we describe a variant of our model that can predict continuous real valued coordinates.

The key obstacle to overcome is *multimodality*: if the network is unsure whether it should predict a coordinate value of a or b, we wish to predict a distribution that splits its mass between a and b, rather than predicting the single value $\frac{a+b}{2}$. In the model where everything is snapped to a discrete grid, supporting this multimodality falls out naturally from our parameterization of the network predictions (i.e., the network predicts the parameters of a multinomial distribution). To predict continuous real valued coordinates we turn to Mixture Density Networks (MDN: (3)). In an MDN, a distribution over a real-valued random variable is parameterized using a mixture of Gaussians, and the deep network predicts the parameters of the Gaussian mixture.

Concretely, we modify our autoregressive drawing command decoder to predict distributions over real-valued coordinates as:

$$p(t_n|t_{1:(n-1)}) = \text{MDN}_{t_1,n}(a(f|t_{1:(n-1)}) \oplus \bigoplus_{j<n} t_j), \text{ if } n^{\text{th}} \text{ token is continuous} \tag{12}$$

Compare this equation with Equation 10 to see that we have only replaced a draw from a multinomial (whose parameters are predicted by an MLP) with a draw from a mixture of Gaussians (whose parameters are predicted by an MDN). Otherwise the two models are identical.

For an MDN i with K mixture components that takes as input x, we parameterize it's output distribution as:

$$\text{MDN}_i(x) = \sum_{1 \leq k \leq K} \pi_{i,k}(x) \times \mathcal{N}(\mu_{i,k}(x), \sigma^2_{i,k}(x)) \tag{13}$$

$$\mu_{i,k}(x) = \text{sigmoid}(W^{\mu_{i,k}} x + b^{\mu_{i,k}} x) \tag{14}$$

$$\sigma^2_{i,k}(x) = \log\left(1 + \exp\left(W^{\sigma^2_{i,k}} x + b^{\sigma^2_{i,k}} x\right)\right) \tag{15}$$

$$\pi_{i,k}(x) = \frac{\exp\left(W^{\pi_{i,k}} x + b^{\pi_{i,k}} x\right)}{\sum_{k'} \exp\left(W^{\pi_{i,k'}} x + b^{\pi_{i,k'}} x\right)} \tag{16}$$

where W with a superscript is a learned weight matrix and b is a learned bias vector. Notice that Equation 14 normalizes the predicted means to be within $[0, 1]$: this is because we wish to constrain the predicted coordinates to lie within the plane $[0, 1]^2$. We used $K = 16$ mixture components.

Figure 5 shows the behavior of the MDN variant of our model on noisy synthetic drawings. Contrast these mediocre results with Figure 4 of the main paper to see that although our main model is essentially at ceiling for parsing scenes like these, the MDN variant fares poorly in comparison.

We evaluated the MDN version of our model on hand drawings by (1) performing a beam search in order to find the trace maximizing $\mathbb{P}[T|I]$, and (2) constraining the predicted coordinates to lie on the 16×16 grid. We constrain the predicted coordinates to lie on the grid by integrating the predicted



Figure 5: Left column: LaTeX output corrupted by noise process designed to resemble the variability is introduced by hand drawings. Right columns: samples from the MDN variant of the model.

densities about each grid location. So, using the probability density $p(t_n|t_{1:(n-1)})$ in Eq. 12, we compute a probability mass function $\mathbb{P}[t_n|t_{1:(n-1)}]$ as:

$$\mathbb{P}[t_n = t|t_{1:(n-1)}] = \int_{t-\frac{1}{2}}^{t+\frac{1}{2}} \mathrm{d}t_n \; p(t_n|t_{1:(n-1)}) \tag{17}$$

Even after using Eq. 17 to constrain the predicted coordinates to lie on the 16×16 grid, the MDN variant of the model only produces finished traces for 48/100 of the drawings. See Figure 6 to see the traces recovered by the beam search.

4.5 LSTM Baseline

We compared our deep network with a baseline that models the problem as a kind of image captioning. Given the target image, this baseline produces the program trace in one shot by using a CNN to extract features of the input which are passed to an LSTM which finally predicts the trace token-by-token. This general architecture is used in several successful neural models of image captioning (e.g., (4)).

Concretely, we kept the image feature extractor architecture (a CNN) as in our model, but only passed it one image as input (the target image to explain). Then, instead of using an autoregressive decoder to predict a single drawing command, we used an LSTM to predict a sequence of drawing commands token-by-token. This LSTM had 128 memory cells, and at each time step produced as output the next token in the sequence of drawing commands. It took as input both the image representation and its previously predicted token.

4.6 A learned likelihood surrogate

Our architecture for $L_{\text{learned}}(\text{render}(T_1)|\text{render}(T_2))$ has the same series of convolutions as the network that predicts the next drawing command. We train it to predict two scalars: $|T_1 - T_2|$ and $|T_2 - T_1|$. These predictions are made using linear regression from the image features followed by a ReLU nonlinearity; this nonlinearity makes sense because the predictions can never be negative but could be arbitrarily large positive numbers.

We train this network by sampling random synthetic scenes for T_1, and then perturbing them in small ways to produce T_2. We minimize the squared loss between the network's prediction and the ground



Figure 6: Parsing hand drawings using the MDN variant of our model. Black-on-white: hand drawings. White-on-black, below each hand drawing: the parse inferred by the model.

truth symmetric differences. T_1 is rendered in a "simulated hand drawing" style which we describe next.

5 SIMULATING HAND DRAWINGS

We introduce noise into the LaTeX rendering process by:

- Rescaling the image intensity by a factor chosen uniformly at random from $[0.5, 1.5]$
- Translating the image by ± 3 pixels chosen uniformly random
- Rendering the LaTeX using the `pencildraw` style, which adds random perturbations to the paths drawn by LaTeXin a way designed to resemble a pencil.
- Randomly perturbing the positions and sizes of primitive LaTeXdrawing commands

6 LIKELIHOOD SURROGATE FOR SYNTHETIC DATA

For synthetic data (e.g., LaTeX output) it is relatively straightforward to engineer an adequate distance measure between images, because it is possible for the system to discover drawing commands that exactly match the pixels in the target image. We use:

$$-\log L(I_1|I_2) = \sum_{1\leq x\leq 256} \sum_{1\leq y\leq 256} |I_1[x,y] - I_2[x,y]| \begin{cases} \alpha, \text{ if } \mathrm{I}_1[x,y] > I_2[x,y] \\ \beta, \text{ if } \mathrm{I}_1[x,y] < I_2[x,y] \\ 0, \text{ if } \mathrm{I}_1[x,y] = I_2[x,y] \end{cases} \tag{18}$$

where α, β are constants that control the trade-off between preferring to explain the pixels in the image (at the expense of having extraneous pixels) and not predicting pixels where they don't exist (at the expense of leaving some pixels unexplained). Because our sampling procedure incrementally constructs the scene part-by-part, we want $\alpha > \beta$. That is, it is preferable to leave some pixels unexplained; for once a particle in SMC adds a drawing primitive to its trace that is not actually in the latent scene, it can never recover from this error. In our experiments on synthetic data we used $\alpha = 0.8$ and $\beta = 0.04$.

7 GENERATING SYNTHETIC TRAINING DATA

We generated synthetic training data for the neural network by sampling LaTeX code according to the following generative process: First, the number of objects in the scene are sampled uniformly from 1 to 12. For each object we uniformly sample its identity (circle, rectangle, or line). Then we sample the parameters of the circles, than the parameters of the rectangles, and finally the parameters of the lines; this has the effect of teaching the network to first draw the circles in the scene, then the rectangles, and finally the lines. We furthermore put the circle (respectively, rectangle and line) drawing commands in order by left-to-right, bottom-to-top; thus the training data enforces a canonical order in which to draw any scene.

To make the training data look more like naturally occurring figures, we put a Chinese restaurant process prior (5) over the values of the X and Y coordinates that occur in the execution trace. This encourages reuse of coordinate values, and so produces training data that tends to have parts that are nicely aligned.

In the synthetic training data we excluded any sampled scenes that had overlapping drawing commands. As shown in the main paper, the network is then able to generalize to scenes with, for example, intersecting lines or lines that penetrate a rectangle.

When sampling the endpoints of a line, we biased the sampling process so that it would be more likely to start an endpoint along one of the sides of a rectangle or at the boundary of a circle. If n is the number of points either along the side of a rectangle or at the boundary of a circle, we would sample an arbitrary endpoint with probability $\frac{2}{2+n}$ and sample one of the "attaching" endpoints with probability $\frac{1}{2+n}$.

See figure 7 for examples of the kinds of scenes that the network is trained on.



Figure 7: Example synthetic training data

For readers wishing to generate their own synthetic training sets, we refer them to our source code at: `redactedForAnonymity.com`.

8 THE COST FUNCTION FOR PROGRAMS

We seek the minimum cost program which evaluates to (produces the drawing primitives in) an execution trace T:

$$\text{program}(T) = \underset{\substack{p \in \text{DSL} \\ p \text{ evaluates to } T}}{\arg\min} \quad \text{cost}(p) \tag{19}$$

Programs incur a cost of 1 for each command (primitive drawing action, loop, or reflection). They incur a cost of $\frac{1}{3}$ for each unique coefficient they use in a linear transformation beyond the first coefficient. This encourages reuse of coefficients, which leads to code that has translational symmetry; rather than provide a translational symmetry operator as we did with reflection, we modify what is effectively a prior over the space of program so that it tends to produce programs that have this symmetry.

Programs also incur a cost of 1 for having loops of constant length 2; otherwise there is often no pressure from the cost function to explain a repetition of length 2 as being a reflection rather a loop.

9 FULL RESULTS ON DRAWINGS DATA SET

Below we show our full data set of drawings. The leftmost column is a hand drawing. The middle column is a rendering of the most likely trace discovered by the neurally guided SMC sampling scheme. The rightmost column is the program we synthesized from a ground truth execution trace of the drawing. Note that because the inference procedure is stochastic, the top one most likely sample can vary from run to run. Below we report a representative sample from a run with 2000 particles.





```
line(6,2,6,3,
arrow = False,solid = True);
line(6,2,3,2,
arrow = True,solid = True);
reflect(y = 9){
line(3,7,5,5,
arrow = True,solid = True);
rectangle(1,1,3,3);
rectangle(5,3,7,6);
rectangle(0,0,8,9)
}
```





```
for (i < 2){
line(8,8,3,8,
arrow = True,solid = False);
line(-2 * i + 12,5,-2 * i + 13,5
arrow = True,solid = True);
line(6,5,7,5,
arrow = True,solid = True);
line(3,-6 * i + 8,5,-2 * i + 6,
arrow = True,solid = True);
rectangle(-2 * i + 13,4,-2 * i +
rectangle(1,-6 * i + 7,3,-6 * i
};
circle(8,5);
rectangle(5,3,6,7);
rectangle(0,0,10,10);
line(8,6,8,8,
arrow = False,solid = False)
```





```
reflect(y = 7){
line(2,6,4,4,
arrow = True,solid = True);
rectangle(0,0,2,2)
};
rectangle(4,2,6,5)
```





```
line(7,5,9,5,
arrow = True,solid = True);
rectangle(5,3,7,7);
rectangle(0,0,12,10);
reflect(y = 10){
circle(10,5);
line(3,2,5,4,
arrow = True,solid = True);
rectangle(1,1,3,3)
}
```





```
line(10,1,2,1,
arrow = True,solid = False);
line(10,1,10,3,
arrow = False,solid = False);
line(7,4,9,4,
arrow = True,solid = True);
reflect(y = 8){
circle(10,4);
line(2,1,4,3,
arrow = True,solid = True);
rectangle(4,2,7,6);
rectangle(0,6,2,8)
}
```





```
line(12,9,12,0,
arrow = True,solid = True);
rectangle(9,3,11,9);
rectangle(6,5,8,9);
rectangle(0,7,2,9);
rectangle(3,8,5,9)
```



```
for (i < 3){
for (j < (1*i + 1)){
if (j > 0){
line(3 * j + -3,3 * i + -2,3 * j
arrow = False,solid = True);
line(0,3 * j + -2,3 * j + -3,4,
arrow = False,solid = True)
}
rectangle(2,0,5,3)
}
}
```





```
for (i < 3){
circle(-3 * i + 7,1);
circle(-3 * i + 7,6);
line(-3 * i + 7,-1 * i + 4,-3 *
arrow = False,solid = True)
}
```

```
line(0,0,0,4,
arrow = False,solid = True)
```

```
line(6,0,0,0,
arrow = True,solid = True)
```



```
rectangle(0,0,3,4)
```



```
circle(1,1)
```





```
reflect(x = 7){
circle(6,1);
line(6,2,6,5,
arrow = False,solid = True);
rectangle(5,5,7,7)
};
line(2,6,5,6,
arrow = False,solid = True);
line(2,1,5,1,
arrow = False,solid = True)
```





```
line(3,2,1,2,
arrow = True,solid = True);
line(0,3,2,3,
arrow = True,solid = True);
line(5,0,3,0,
arrow = True,solid = True);
line(2,1,4,1,
arrow = True,solid = True)
```





```
rectangle(6,0,7,1);
for (i < 3){
rectangle(-2 * i + 4,2 * i + 2,-
rectangle(-2 * i + 4,2 * i,-2 *
}
```

```
line(3,0,5,0,
arrow = False,solid = True);
line(1,2,3,2,
arrow = False,solid = True);
line(0,3,2,3,
arrow = False,solid = False);
line(2,1,4,1,
arrow = False,solid = False)
```





```
circle(9,1);
for (i < 3){
circle(-2 * i + 7,3 * i + 4);
circle(-2 * i + 5,3 * i + 1);
line(-2 * i + 6,3 * i + 1,-2 * i
arrow = False,solid = True);
line(-2 * i + 7,3 * i + 3,-2 * i
arrow = False,solid = True)
}
```





```
for (i < 3){
line(2 * i + 3,-3 * i + 9,2 * i
arrow = True,solid = True);
line(2 * i + 3,-3 * i + 9,2 * i
arrow = True,solid = True);
rectangle(2 * i + 2,-3 * i + 9,2
rectangle(2 * i,-3 * i + 6,2 * i
};
rectangle(8,0,10,2)
```





```
for (i < 2){
circle(2 * i + 1,-3 * i + 6);
circle(-3 * i + 7,2 * i + 3);
circle(2 * i + 5,1)
}
```





```
line(4,4,2,2,
arrow = True,solid = True);
rectangle(0,0,2,2);
rectangle(3,4,5,6)
```





```
for (i < 3){
line(-4 * i + 9,4,-4 * i + 9,2,
arrow = True,solid = True);
for (j < (1*i + 2)){
if (j > 0){
circle(-4 * j + 13,-4 * i + 9);
line(-4 * i + 12,5,-4 * i + 10,5
arrow = True,solid = True)
}
rectangle(0,4,2,6)
}
}
```





```
circle(1,5);
line(4,1,2,1,
arrow = True,solid = True);
line(8,1,6,1,
arrow = True,solid = True);
for (i < 3){
line(4 * i + 1,2,4 * i + 1,4,
arrow = True,solid = True);
rectangle(4,4,6,6);
rectangle(4 * i,0,4 * i + 2,2)
};
rectangle(8,4,10,6)
```





```
for (i < 3){
line(4 * i + 1,4,4 * i + 1,2,
arrow = True,solid = True);
for (j < 2){
line(4 * j + 4,5,4 * j + 2,5,
arrow = True,solid = True);
rectangle(4 * i,-4 * j + 4,4 * i
}
}
```





```
for (i < 3){
line(4 * i + 1,2,4 * i + 1,4,
arrow = True,solid = True);
for (j < 2){
circle(4 * i + 1,4 * j + 1);
line(4 * j + 4,1,4 * j + 2,1,
arrow = True,solid = True)
}
}
```





```
line(5,7,5,6,
arrow = True,solid = True);
line(3,3,3,2,
arrow = True,solid = True);
line(1,7,1,6,
arrow = True,solid = True);
rectangle(0,3,6,6);
rectangle(2,0,4,2);
rectangle(0,7,6,9)
```



```
line(6,1,5,1,
arrow = True,solid = True);
for (i < 3){
line(3,1,2,1,
arrow = True,solid = True);
rectangle(3 * i,0,3 * i + 2,2)
}
```



```
for (i < 3){
circle(1,-4 * i + 9)
};
line(1,4,1,2,
arrow = True,solid = True);
line(1,8,1,6,
arrow = True,solid = True)
```

```
reflect(y = 2){
line(0,1,1,2,
arrow = False,solid = True);
line(1,0,2,1,
arrow = False,solid = True)
}
```



```
line(0,0,0,2,
arrow = False,solid = True);
line(0,2,2,2,
arrow = False,solid = True)
```



```
for (i < 3){
line(1 * i,-2 * i + 4,1 * i,-1 *
arrow = False,solid = True);
line(1 * i,-1 * i + 6,2 * i + 2,
arrow = False,solid = True)
}
```





```
circle(5,2);
circle(5,4);
rectangle(4,1,6,5);
reflect(y = 5){
circle(1,4);
rectangle(0,3,2,5)
}
```





```
for (i < 3){
for (j < (1*i + 1)){
circle(3 * i + 1,-2 * j + 5)
};
rectangle(3 * i,-2 * i + 4,3 * i
}
```





```
circle(5,5);
line(2,5,4,5,
arrow = False,solid = True);
rectangle(0,0,5,3);
rectangle(0,4,2,6)
```





```
line(0,0,0,3,
arrow = False,solid = True);
line(6,0,6,3,
arrow = False,solid = True);
line(0,3,6,3,
arrow = False,solid = False);
line(0,0,6,0,
arrow = False,solid = False)
```



```
for (i < 2){
line(2 * i,-2 * i + 5,2,5,
arrow = False,solid = True);
line(1,2,2 * i + 1,-2 * i + 4,
arrow = False,solid = True);
line(2 * i + 3,-2 * i + 3,5,3,
arrow = False,solid = True);
line(4,0,2 * i + 4,-2 * i + 2,
arrow = False,solid = True)
}
```





```
circle(6,1);
circle(1,1);
circle(1,6);
line(2,6,6,2,
arrow = True,solid = True);
line(1,5,1,2,
arrow = True,solid = True)
```





```
rectangle(5,5,9,9);
rectangle(0,0,4,4);
for (i < 2){
rectangle(1 * i + 7,-2 * i + 2,9
rectangle(0,-3 * i + 8,1 * i + 1
}
```





```
circle(1,8);
line(5,2,5,5,
arrow = False,solid = True);
line(1,7,3,5,
arrow = False,solid = True);
rectangle(4,0,6,2);
rectangle(0,5,6,9)
```





```
for (i < 3){
for (j < 3){
if (j > 0){
line(3 * j + -1,3 * i + 1,3 * j,
arrow = False,solid = True);
line(3 * i + 1,3 * j + -1,3 * i
arrow = False,solid = True)
}
circle(3 * i + 1,3 * j + 1)
}
}
```





```
for (i < 3){
for (j < 3){
if (j > 0){
line(3 * i + 1,3 * j + -1,3 * i
arrow = False,solid = True);
line(3 * j + -1,3 * i + 1,3 * j,
arrow = False,solid = True)
}
rectangle(3 * i,3 * j,3 * i + 2,
}
}
```



```
for (i < 3){
circle(-3 * i + 7,1)
}
```





```
for (i < 3){
rectangle(-2 * i + 4,0,-2 * i +
}
```

```
line(4,0,4,1,
arrow = False,solid = False);
line(0,0,0,5,
arrow = False,solid = False);
line(4,1,4,5,
arrow = False,solid = False)
```

```
line(0,0,0,5,
arrow = False,solid = True);
line(4,0,4,5,
arrow = False,solid = True)
```



```
reflect(x = 12){
circle(4,1);
line(2,1,3,1,
arrow = False,solid = True);
rectangle(0,0,2,2)
}
```





```
circle(7,6);
reflect(y = 12){
line(4,6,6,6,
arrow = True,solid = True);
line(2,10,2,8,
arrow = True,solid = True);
rectangle(1,0,3,2)
};
rectangle(0,4,4,8)
```





```
reflect(y = 9){
reflect(x = 9){
circle(8,8);
line(3,8,6,8,
arrow = False,solid = True);
line(1,3,1,6,
arrow = False,solid = True)
}
}
```





```
reflect(x = 11){
rectangle(9,4,10,7);
reflect(y = 11){
rectangle(8,0,11,3);
rectangle(4,9,7,10)
}
}
```



```
for (i < 3){
line(2 * i,-2 * i + 5,2 * i + 2,
arrow = False,solid = True);
line(2 * i + 1,-2 * i + 4,2 * i
arrow = False,solid = True)
}
```





```
rectangle(4,1,6,2);
rectangle(7,0,9,2);
reflect(y = 10){
rectangle(0,0,3,3);
rectangle(1,4,2,6)
}
```





```
line(7,4,9,4,
arrow = True,solid = True);
line(8,3,7,3,
arrow = True,solid = True);
reflect(y = 7){
line(2,1,4,3,
arrow = True,solid = True);
rectangle(0,0,2,2)
};
line(8,3,9,3,
arrow = False,solid = True);
rectangle(9,2,12,5);
rectangle(4,2,7,5)
```



```
for (i < 3){
rectangle(2 * i,2 * i,2 * i + 3,
}
```





```
circle(4,10);
for (i < 3){
circle(3 * i + 1,1);
circle(3 * i + 1,5);
line(4,9,3 * i + 1,6,
arrow = True,solid = True);
line(3 * i + 1,4,3 * i + 1,2,
arrow = True,solid = True)
}
```





```
line(2,8,2,6,
arrow = True,solid = True);
line(4,8,4,0,
arrow = True,solid = True);
line(6,8,6,4,
arrow = True,solid = True);
line(0,8,8,8,
arrow = False,solid = True)
```





```
line(2,3,2,5,
arrow = False,solid = True);
rectangle(0,0,4,8);
rectangle(1,1,3,3);
rectangle(1,5,3,7)
```



```
circle(1,5);
line(1,4,1,2,
arrow = True,solid = True);
rectangle(0,0,2,2)
```





```
rectangle(0,0,6,2);
reflect(x = 6){
for (i < 3){
circle(5,2 * i + 4);
circle(2 * i + 1,1);
rectangle(4,3,6,9)
}
}
```





```
for (i < 3){
for (j < 3){
circle(4 * i + 1,-3 * j + 7)
}
}
```





```
line(8,0,0,0,
arrow = True,solid = True);
line(8,0,8,7,
arrow = True,solid = True);
for (i < 3){
rectangle(-2 * i + 6,0,-2 * i +
}
```




```
line(4,0,0,0,
arrow = False,solid = False)
```





```
line(2,4,4,4,
arrow = True,solid = True);
line(6,7,5,5,
arrow = True,solid = True);
for (i < 2){
circle(-2 * i + 7,-3 * i + 7);
circle(3 * i + 4,1);
line(5,3,3 * i + 4,2,
arrow = True,solid = True);
rectangle(0,3,2,5)
}
```





```
circle(2,1);
circle(6,1);
line(5,1,3,1,
arrow = True,solid = True);
rectangle(0,0,7,2)
```



```
rectangle(5,0,8,3);
rectangle(0,2,1,3);
rectangle(2,1,4,3)
```





```
for (i < 3){
rectangle(-1 * i + 2,-1 * i + 2,
}
```





```
reflect(y = 6){
line(2,5,4,5,
arrow = False,solid = True);
reflect(x = 6){
line(5,2,5,4,
arrow = False,solid = True);
rectangle(0,4,2,6)
}
}
```





```
reflect(y = 6){
reflect(x = 6){
circle(1,1);
line(5,2,5,4,
arrow = False,solid = True)
};
line(2,1,4,1,
arrow = False,solid = True)
}
```



```
for (i < 3){
line(1 * i,-1 * i + 2,-1 * i + 7
arrow = False,solid = True)
}
```





```
line(1,5,5,1,
arrow = False,solid = True);
line(1,4,5,0,
arrow = False,solid = True);
rectangle(0,4,1,5);
rectangle(5,0,6,1)
```



```
for (i < 3){
circle(-4 * i + 9,1);
rectangle(-4 * i + 8,0,-4 * i +
}
```





```
reflect(x = 5){
circle(4,1);
line(4,4,4,2,
arrow = True,solid = True)
};
rectangle(0,4,5,6)
```





```
circle(3,1);
reflect(x = 6){
circle(5,5);
circle(1,9);
line(5,4,3,2,
arrow = True,solid = True);
line(5,8,2,5,
arrow = True,solid = True);
line(1,8,1,6,
arrow = True,solid = True)
}
```





```
for (i < 3){
line(7,1,5 * i + 2,3,
arrow = True,solid = True);
for (j < (1*i + 1)){
if (j > 0){
line(5 * j + -1,9,5 * i,5,
arrow = True,solid = True)
}
line(5 * j + 2,5,5 * j + 2,9,
arrow = True,solid = True)
};
rectangle(5 * i,3,5 * i + 4,5);
rectangle(5 * i,9,5 * i + 4,10)
};
rectangle(2,0,12,1)
```





```
reflect(y = 8){
for (i < 3){
circle(-3 * i + 7,-3 * i + 7)
};
rectangle(2,2,3,3);
rectangle(5,5,6,6)
}
```





```
line(10,8,12,4,
arrow = True,solid = True);
line(6,8,8,4,
arrow = True,solid = True);
for (i < 3){
line(4 * i + 5,5,4 * i + 5,7,
arrow = True,solid = True);
line(4 * i + 5,1,4 * i + 5,3,
arrow = True,solid = True);
rectangle(4 * i + 4,3,4 * i + 6,
rectangle(4 * i + 4,7,4 * i + 6,
line(2,1,13,1,
arrow = False,solid = True)
};
rectangle(0,0,2,8)
```





```
for (i < 3){
for (j < 3){
circle(2 * j + 1,2 * i + 1)
}
};
rectangle(2,2,4,4);
rectangle(0,0,6,6)
```





```
for (i < 4){
circle(4 * i + 1,1);
circle(4 * i + 1,5);
for (j < 3){
line(4 * i + 1,4,4 * i + 1,2,
arrow = True,solid = True);
line(4 * j + 2,5,4 * j + 4,5,
arrow = True,solid = True)
}
}
```





```
reflect(x = 8){
circle(4,1);
circle(1,8);
line(0,2,4,5,
arrow = False,solid = True);
line(4,5,4,10,
arrow = False,solid = True)
}
```





```
circle(9,8);
circle(5,1);
circle(1,8);
reflect(x = 10){
line(6,1,9,3,
arrow = False,solid = True);
line(2,8,4,8,
arrow = False,solid = True);
line(9,5,9,7,
arrow = False,solid = True);
rectangle(0,3,2,5)
};
rectangle(4,7,6,9)
```





```
line(3,2,5,4,
arrow = True,solid = True);
line(6,6,6,5,
arrow = True,solid = True);
line(8,3,7,4,
arrow = True,solid = True);
line(4,0,12,8,
arrow = False,solid = True);
line(0,6,12,6,
arrow = False,solid = True);
line(0,8,8,0,
arrow = False,solid = True)
```





```
for (i < 3){
circle(4 * i + 1,13);
circle(5,-4 * i + 9);
circle(4 * i + 1,9);
line(4 * i + 1,12,4 * i + 1,10,
arrow = True,solid = True);
line(5,-4 * i + 12,5,-4 * i + 10
arrow = True,solid = True)
};
line(9,8,6,5,
arrow = True,solid = True);
line(1,8,4,5,
arrow = True,solid = True)
```





```
reflect(x = 14){
circle(11,10);
circle(3,4);
circle(7,1);
reflect(y = 20){
circle(13,7);
circle(9,7)
};
line(3,3,7,2,
arrow = True,solid = True);
line(10,10,5,8,
arrow = True,solid = True);
reflect(x = 6){
line(5,12,3,11,
arrow = True,solid = True);
line(1,6,3,5,
arrow = True,solid = True);
line(3,9,5,8,
arrow = True,solid = True)
}
}
```



```
circle(1,1);
circle(4,1);
rectangle(6,0,8,2);
rectangle(9,0,11,2)
```





```
Solver timeout
```





```
reflect(x = 10){
circle(5,1);
circle(2,4);
line(2,3,5,2,
arrow = True,solid = True);
reflect(x = 16){
circle(9,7);
line(9,6,8,5,
arrow = True,solid = True)
}
}
```





```
Solver timeout
```





```
for (i < 4){
if (i > 0){
line(1,3 * i,1,3 * i + -1,
arrow = True,solid = True)
}
circle(1,3 * i + 1)
}
```





```
rectangle(5,0,8,3);
rectangle(0,5,3,8);
for (i < 2){
rectangle(1 * i + 6,3 * i + 4,8,
rectangle(0,2 * i,1 * i + 1,3 *
}
```





```
reflect(x = 8){
rectangle(0,0,1,1);
rectangle(5,5,8,8);
rectangle(0,2,2,4)
}
```





```
for (i < 3){
rectangle(-2 * i + 4,-1 * i + 2,
}
```





```
circle(9,5);
line(3,1,8,1,
arrow = True,solid = True);
line(8,5,7,5,
arrow = True,solid = True);
line(9,8,0,8,
arrow = True,solid = True);
line(9,2,9,4,
arrow = True,solid = True);
line(12,1,10,1,
arrow = True,solid = True);
line(9,2,10,1,
arrow = False,solid = True);
line(12,1,12,5,
arrow = False,solid = True);
reflect(x = 6){
line(6,5,4,5,
arrow = True,solid = True)
};
rectangle(2,4,4,6);
rectangle(1,0,13,9);
line(9,6,9,8,
arrow = False,solid = True);
line(6,4,7,5,
arrow = False,solid = True);
line(10,5,12,5,
arrow = False,solid = True);
line(3,1,3,4,
arrow = False,solid = True)
```





```
circle(6,2);
for (i < 3){
circle(5 * i + 1,7)
};
line(5,7,2,7,
arrow = True,solid = True);
line(6,6,6,3,
arrow = True,solid = True);
line(10,7,7,7,
arrow = True,solid = True);
rectangle(4,0,8,9)
```



```
reflect(x = 5){
reflect(y = 5){
line(0,5,2,5,
arrow = False,solid = True);
line(0,3,0,5,
arrow = False,solid = True)
}
}
```



```
for (i < 3){
reflect(x = 14){
circle(9,4 * i + 1);
line(10,4 * i + 1,12,4 * i + 1,
arrow = False,solid = True);
rectangle(0,4 * i,2,4 * i + 2)
}
}
```



```
reflect(x = 10){
line(5,6,1,8,
arrow = True,solid = True);
line(9,2,5,4,
arrow = True,solid = True);
for (i < 3){
circle(4 * i + 1,4 * i + 1)
}
}
```





```
reflect(x = 12){
line(6,2,6,3,
arrow = True,solid = True);
line(2,7,5,4,
arrow = True,solid = True);
line(0,0,9,9,
arrow = False,solid = True)
};
line(0,2,12,2,
arrow = False,solid = True)
```





```
for (i < 3){
for (j < 3){
if (j > 0){
circle(6 * i + -5,-5 * j + 16);
line(6 * i + -5,5,4,2,
arrow = True,solid = True);
line(6 * j + -5,10,6 * i + -5,7,
arrow = True,solid = True)
}
circle(4,1)
}
}
```





```
reflect(y = 10){
circle(1,9);
for (i < 4){
circle(-2 * i + 9,-2 * i + 9)
}
}
```





```
for (i < 3){
circle(1,-4 * i + 9);
circle(5,-4 * i + 9);
for (j < 3){
if (j > 0){
line(4 * i + -3,-4 * j + 10,4 *
arrow = False,solid = True)
}
line(2,-4 * j + 9,4,-4 * j + 9,
arrow = False,solid = True)
}
}
```





```
circle(2,2);
circle(2,6);
circle(2,11);
line(2,5,2,3,
arrow = True,solid = True);
line(2,10,2,7,
arrow = True,solid = True);
rectangle(0,0,4,9)
```





```
for (i < 2){
circle(4,6 * i + 1);
circle(1,6 * i + 4);
rectangle(0,6 * i,2,6 * i + 2);
rectangle(3,6 * i + 3,5,6 * i +
}
```

REFERENCES

[1] Michael AA Cox and Trevor F Cox. Multidimensional scaling. *Handbook of data visualization*, pages 315–347, 2008.

[2] Max Jaderberg, Karen Simonyan, Andrew Zisserman, et al. Spatial transformer networks. In *Advances in Neural Information Processing Systems*, pages 2017–2025, 2015.

[3] Christopher M. Bishop. Mixture Density Networks. Technical report, 1994.

[4] Oriol Vinyals, Alexander Toshev, Samy Bengio, and Dumitru Erhan. Show and tell: A neural image caption generator. In *Proceedings of the IEEE conference on computer vision and pattern recognition*, pages 3156–3164, 2015.

[5] Samuel J Gershman and David M Blei. A tutorial on bayesian nonparametric models. *Journal of Mathematical Psychology*, 56(1):1–12, 2012.